



Meeting Agenda

Zoning Board of Adjustment

Tuesday, June 20, 2023

5:00 PM

Ankeny City Council Chambers

1250 SW District Drive, Second Floor, Ankeny, Iowa

Matt Ott, Chair

Jeffrey Baxter, Vice Chair

Nichole Sungren

Kristi Tomlinson

Brett Walker

Zoning Board of Adjustment regular meetings are the first and third Tuesday of each month at 5:00 p.m. All Board of Adjustment meetings are open to the public. Assistive Listening Devices (ALD) are available for persons with impaired hearing.

CALL TO ORDER

A. ROLL CALL

B. AMENDMENTS TO AGENDA

C. MINUTES

Minutes of the May 2, 2023 regular meeting.

D. COMMUNICATIONS/CORRESPONDENCE

E. BUSINESS ITEMS

PUBLIC HEARINGS Public Hearings are held during the Zoning Board of Adjustment's regular meetings. Those who wish to speak will be requested to provide their name and address for the record when called upon. The order of proceedings for each application will be as follows: 1). The applicant will present testimony and evidence regarding their request; 2). City staff will summarize the project and present their findings; 3). Testimony may be heard from any members of the audience who wish to speak in support of or in opposition to the appeal; 4). The Board will give the applicant and the city staff an opportunity to present concluding summaries and arguments. At the conclusion of all public testimony, the Board will close the public hearing. The Board will discuss the issues and evidence and come to a decision. The applicant or appellant may withdraw their application or appeal at any time prior to the decision by the Zoning Board of Adjustment.

#23-11

City of Ankeny

for property located at

3755 NW Irvinedale Drive

PARCEL 2018-156 COM NW COR PARC E THN E 50F TO POB THN E 422.24F

S 170.36F W 127.57F W 295.16F N 172.57F TO POB BNG PRT PARCEL E

BK 15735 PG 812 SW 1/4 SW 1/4 SEC 3-80-24

RE: Variance - Height

#23-12

Bryon and Larissa Weyer

for property located at

2506 NE 17th Street

Lot 21, Deer Creek Estates Plat 13

RE: Variance - Rear Yard Setback

F. OLD BUSINESS:

G. NEW BUSINESS

H. REPORTS

Renewed Special Use Permits

#10-06 Lindo Jalisco Mexican, 1810 SW White Birch Circle, Ste. 118

#21-06 El Molcajete, 301 E 1st Street

#16-16 Guadalajara Mexican Restaurant, 202 SE Delaware Avenue

#18-04(2019) Who's on First, 810 E 1st Street

I. ADJOURNMENT



ZONING BOARD OF ADJUSTMENT

June 20, 2023

5 : 00 PM



ORIGINATING DEPARTMENT:

Planning and Building

COUNCIL GOAL:

ACTION REQUESTED:

Motion

LEGAL:

SUBJECT:

Minutes of the May 2, 2023 regular meeting.

EXECUTIVE SUMMARY:

FISCAL IMPACT: **No**

STAFF RECOMMENDATIONS:

PREVIOUS COUNCIL/COMMISSION/BOARD ACTION(S):

PUBLIC OUTREACH EFFORTS:

ACTION REQUESTED:

ADDITIONAL INFORMATION:

ATTACHMENTS:

Click to download

 [ZBOA Minutes 2023-05-02](#)

Meeting Minutes
Zoning Board of Adjustment
Tuesday, May 2, 2023
Ankeny City Council Chambers
1250 SW District Drive, Second Floor, Ankeny, Iowa

CALL TO ORDER

Chair Matt Ott called the May 2, 2023 regular meeting of the Zoning Board of Adjustment to order at 5:00 p.m.

ROLL CALL

Members present: Jeff Baxter, Matt Ott, Kristi Tomlinson, and Nichole Sungren. Absent: Brett Walker.
Staff: E.Jensen, E.Carstens, D.Gervais, L.Hutzell, R.Kirschman.

AMENDMENTS TO THE AGENDA

There were no amendments to the agenda.

MINUTES OF THE APRIL 18, 2023 REGULAR MEETING

Motion by K.Tomlinson to approve the April 18, 2023 meeting minutes as submitted. Second by N.Sungren. All voted aye. Motion carried 4 – 0 .

COMMUNICATIONS / CORRESPONDENCE

There were no communications.

BUSINESS ITEMS

PUBLIC HEARINGS:

#23-08

Kara Bixby Rodriguez & Joel Rodriguez

for property located at

2943 SW 3rd Street

-EX W67F & N 67F ON W LN & N70.59F ON ELN RD EASS140F N 798.1F

W 356.14F NW 1/4 SEC 22-80-24

RE: Variance - Front Yard Setback

Chair M.Ott opened the public hearing.

Kara Bixby, 2943 SW 3rd Street said that they purchased their home last month and are requesting a variance to allow a front yard setback of 23-feet from the roadway easement instead of a 35-foot setback. She noted that the home was built in the 1970's. She stated that they were under contract to purchase the home and when they started the process to purchase, they were notified that there was a zoning issue with the property. Kara Bixby further stated that they decided to continue with the purchase and work towards resolving the zoning issue. She respectfully asked for the Board to approve the request.

D.Gervais reported that the applicant is requesting a variance to allow the existing home to encroach approximately 12-feet into the 35-foot front yard setback for the subject property at 2943 SW 3rd Street, which is located south of SW 3rd Street and east of SW Irvinedale Drive. She noted that the subject property is not a platted lot. She stated that the subject property is zoned C-2, General Retail, Highway-Oriented, and Central Business Commercial District with neighboring properties to the north, east, and south being zoned C-2. The neighboring properties west of SW Irvinedale Drive are unincorporated and under Polk County jurisdiction, zoned Rural Residential. D.Gervais provided the Board with the history of the property and home starting back in 1973, which was when the home was to be constructed on the property. She said that during staff's research; they found that the home was partially constructed in the Roadway Easement area for SW 3rd Street. She stated that after much discussion with other City departments, including public works and municipal utilities, the recommendation was that at least 30-feet of the Roadway Easement should be retained and the private utility companies required an additional 3-feet for a total of 33-feet for the south side of the Roadway Easement, measured from the street centerline of SW 3rd Street. D.Gervais stated that on May 1, 2023, City Council approved the ordinance vacating this portion of the Roadway Easement, allowing for a free and clear 23-foot front yard setback. All property owners within 250-feet of the subject property were notified and to date, staff has not received any correspondence either for or against the request. Staff does not have concern about the future impact of this variance request on the existing neighborhood; and recommend that the Zoning Board of

Adjustment grant a variance to Ankeny Municipal Code Section 192.09(3)(D) to allow a 23-foot front yard setback for the existing home at 2943 SW 3rd Street. Staff's position is based on a determination that the existing front yard setback from home does not impair adequate supply of air and light, does not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code.

There was no one in the audience to speak for or against the requests.

Motion by J.Baxter to close the public hearing, and receive and file documents. Second by M.Ott. All voted aye. Motion carried 4 – 0.

The Board has no concerns with the request.

Board Action on Filing #23-08 property located at 2943 SW 3rd Street

Motion by M.Ott that the Zoning Board of Adjustment grant a variance to Ankeny Municipal Code Section 192.09(3)(D) to allow a 23-foot front yard setback for the existing home at 2943 SW 3rd Street. The Board's decision is based on a determination that the existing front yard setback from home does not impair adequate supply of air and light, does not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code. Second by N.Sungren. All voted aye. Motion carried 4 – 0.

#23-09 and #23-10

Ralph Grout

for property located at

1101 NE Trilein Drive

Lot 9, Barclay Plat 1

RE: #23-09 Variance - Rear Yard Setback, Sunroom

#23-10 Variance - Rear Yard Setback, Deck

Chair M.Ott opened the public hearing.

Ralph Grout, 1101 NE Trilein Drive, said that they bought the house last August and decided this year to add a deck. He stated that they were not aware that there was no permit pulled to screen in the deck, which is currently fully enclosed. Ralph Grout said that they are asking for a variance for the screened in deck since it was not approved by the City and a variance for the deck that they would like to build off of the screened in area. He said he would answer any questions the Board may have.

L.Hutzell reported that the subject property is located at 1101 NE Trilein Drive, east of N Ankeny Boulevard and South of NE 18th Street within the northeastern quadrant of Ankeny. She said the property is zoned R-1, One-Family Residence District and contains a single-family home with an attached sunroom on the east side of the .234-acre lot. Neighboring properties in all directions are also zoned R-1, while properties further to the west are zoned R-2. L.Hutzell stated that the home, as it sits today, has a sunroom that sits 12-feet off the east side of the house, creating a 10-foot encroachment into the required 35-foot rear yard setback. She noted that permit records indicate that the house on the subject property was constructed in 1990; however, original plans indicate that the home was built without a sunroom and is setback 37-feet from the rear property line. The existing sunroom also has an exterior staircase 4-feet. She shared that a contractor, on behalf of the property owners, submitted a permit application to construct an uncovered deck attached to the existing sunroom and at that time City staff realized the existing sunroom was never properly permitted and encroaches 10-feet into the required 35-foot rear yard setback. She said that the proposed deck is 216 square feet in size and would sit on the north side of the sunroom with access to the sunroom's existing rear door via a proposed 4-foot wide walkway. L.Hutzell stated that per City code, unenclosed decks are allowed to extend up to twelve feet into the rear yard setback, however staff realized that the sunroom's 10-foot encroachment results in the deck also encroaching 2-feet beyond the 12-feet allowed by code. Staff then informed the applicant that a second variance would be needed to approve the plans for the deck. The staff position is to grant a 10-foot variance to Ankeny Municipal Code Section 192.03(3)(E) to allow a 25-foot rear yard setback for an existing sunroom at 1101 NE Trilein Drive. Staff's position is based on a determination that the decreased rear yard setback from the existing sunroom would not impair adequate supply of air and light, would not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code. It is also staff's position to grant a 2-foot variance to Ankeny Municipal Code Section

196.03(2B)(2), to allow an unenclosed deck to encroach two-feet beyond the allowed 12-feet by code at 1101 NE Trilein Drive. Staff's position is based on a determination that the decreased rear yard setback from the unenclosed deck would not impair adequate supply of air and light, would not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code.

There was no one in the audience to speak for or against the request.

Motion by M.Ott to close the public hearing, and receive and file correspondence received. Second by K.Tomlinson. All voted aye. Motion carried 4 – 0.

The Board had no concerns with the requests.

Board Action on Filing #23-09 property located at 1101 NE Trilein Drive

Motion by J.Baxter that the Zoning Board of Adjustment grant a 10-foot variance to Ankeny Municipal Code Section 192.03(3)(E), to allow for a 25-foot rear yard setback for an existing sunroom at 1101 NE Trilein Drive. The Board's position is based on a determination that the decreased rear yard setback from the existing sunroom does not impair adequate supply of air and light, does not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code. Second by N.Sungren. All voted aye. Motion carried 4 – 0.

Board Action on Filing #23-10 property located at 1101 NE Trilein Drive

Motion by J.Baxter that the Zoning Board of Adjustment grant a 2-foot variance to Ankeny Municipal Code Section 196.03(2B)(2), to allow for an unenclosed deck to encroach two-feet beyond the allowed 12-feet by code at 1101 NE Trilein Drive. The Board's position is based on a determination that the decreased rear yard setback will not impair adequate supply of air and light, will not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code. Second by K.Tomlinson. All voted aye. Motion carried 4 – 0.

NEW BUSINESS

There was no new business.

REPORTS

There were no reports.

There being no further business, meeting adjourned at 5:26 p.m.



Submitted by Eric Carstens, Planning Manager
Zoning Board of Adjustment



ZONING BOARD OF ADJUSTMENT

June 20, 2023

5 : 00 PM

 [Print](#)

ORIGINATING DEPARTMENT:

Planning and Building

COUNCIL GOAL:

Ensure Economic Vitality

ACTION REQUESTED:

Public Hearing

LEGAL:

SUBJECT:

#23-11

City of Ankeny

for property located at

3755 NW Irvinedale Drive

PARCEL 2018-156 COM NW COR PARC E THN E 50F TO POB THN E 422.24F

*S 170.36F W 127.57F W 295.16F N 172.57F TO POB BNG PRT PARCEL E
BK 15735 PG 812 SW 1/4 SW 1/4 SEC 3-80-24*

RE: Variance - Height

EXECUTIVE SUMMARY:

FISCAL IMPACT: **No**

STAFF RECOMMENDATIONS:

PREVIOUS COUNCIL/COMMISSION/BOARD ACTION(S):

PUBLIC OUTREACH EFFORTS:


ACTION REQUESTED:

ADDITIONAL INFORMATION:

ATTACHMENTS:

Click to download	
	#23-11 Applicant Submittal
	#23-11 Staff Report

#23-11



APPLICATION FOR APPEAL ZONING BOARD OF ADJUSTMENT

Applicant is: ☒ Property Owner ☐ Tenant ☐ Other _____

Applicant City of Ankeny, Don Clark, Municipal Utilities Director

Address / Phone # 1210 NW Prairie Ridge Drive, Ankeny IA, 50023, 515-963-3529

E-mail dclark@ankenyiowa.gov

Property Owner City of Ankeny

Address / Phone # 410 W. 1st Street, Ankeny IA, 50023, 515-965-6400

E-mail dclark@ankenyiowa.gov

(Owner must sign the application or submit a letter of authorization)

To the Members of the Board of Adjustment:

I hereby appeal from the decision of the Zoning Administrator rendered on _____ day of _____, 20____

Location (address) of the proposed variance 3755 NW Irvinedale Drive

Legal description (Plat & Lot #) Parcel 2018-156

Zoning C-1 Principal Use of property Vacant land

I request a variation from the current zoning requirement for:

☐ Front Yard ☐ Side Yard ☐ Rear Yard ☐ Fence ☐ Sign ☐ Parking ☒ Height
☐ Other _____

Ankeny Zoning code Section # 192.08.3.D which state(s) 35 feet is maximum height

I would propose the following in lieu of that required: A height variance of 130 feet to allow a water tower of 165 feet in height plus an additional 15 feet of height to allow for a communication antenna for a total of 145 feet height variance.

Attached hereto and made a part of this appeal, I submit the following:

- A statement indicating the reasons for my appeal.
- A drawing showing proposed variance requested.
- A letter of authorization from the owner or lessee, if applicable.

Complete submittals are required for review.


AFFIDAVIT

State of IOWA)ss
County of POLK)

I hereby deposit and say that all of the above statements and the statements contained in the papers submitted herewith are true.

Donald Clark

(Signature of Applicant)



Signed and sworn to before me, this

1st day of May, 20 23

Kathy Dozler
(Notary Public)


Date received May 1, 2023

Paid ☐ Cash ☐ Check # N/A

Office Use Only

Filing # 23-11

Scheduled Meeting Date _____



April 28, 2023

Ankeny Zoning Board of Adjustment
City Council Chambers
1250 SW District Drive
Ankeny, IA 50023

RE: 2.5 Million Gallon Elevated Water Storage Tower
Request for Height Variance

Dear Board Members:

The City of Ankeny is requesting Zoning Board of Adjustment approval of a variance for a new 165-ft tall water tower with possible communication antennas to a maximum of 180 feet. The tower height is set to match the high-water level of both the Ash Water Tower as well as the SW Irvinedale Water Tower to maintain the static water level between the towers. This will balance the water levels within the towers meaning they will work together to handle demands throughout the City of Ankeny without water overflowing or depleting at any one tower.

At the current time, we do not anticipate having the need for cell phone antennas on the tower as there are other cell towers within close proximity. However, the water tower is designed to accommodate their future addition if necessary. We will have a small radio antenna at the top of the tower allowing the City and Des Moines Water Works to monitor water levels within the tower.

I plan to be attending the May 16, 2023, Board of Adjustment meeting and will answer any questions you may have at that time.

Sincerely,

A handwritten signature in blue ink that reads "Don Clark".

Don Clark, P.E.
Director of Municipal Utilities
1210 NW Prairie Ridge Drive
Ankeny, Iowa 50023
Pf/fx/txt: 515-963-3529
DClark@AnkenyIowa.gov



300 E Locust Street, Suite 210
Des Moines, IA 50309-1823
515-280-4940



CITY OF ANKENY

POLK COUNTY, IOWA

NW IRVINEDALE DRIVE - ELEVATED WATER STORAGE TANK

INDEX OF CONTENTS

Project No.
10345779

100% Review Set
March 2023

INDEX OF DRAWINGS

SHEET	FILE	(00) - GENERAL
1	00G000	COVER SHEET
2	00G001	GENERAL ABBREVIATIONS
3	00G002	GENERAL SYMBOLS, PIPING SYSTEMS AND EQUIPMENT IDENTIFICATION LEGEND
4	00G003	GENERAL ELECTRICAL LEGEND
5	00G004	GENERAL INSTRUMENTATION LEGEND

SHEET	FILE	(02) - STANDARD DETAILS
6	02CS01	SITE DETAILS
7	02S001	STRUCTURAL NOTES
8	02S501	TYPICAL CONCRETE DETAILS
9	02S501	WATER MAIN PIPING AND APPURTENANCES DETAILS
10	02DS02	WATER MAIN PIPING AND APPURTENANCES DETAILS
11	02ES01	ELECTRICAL DETAILS
12	02ES02	ELECTRICAL DETAILS


SHEET	FILE	(1D) - SITE PLANNING
13	10V101	EXISTING CONDITIONS AND SURVEY - NORTH
14	10V102	EXISTING CONDITIONS AND SURVEY - SOUTH
15	10C101	SITE LAYOUT PLAN NORTH
16	10C102	SITE LAYOUT PLAN SOUTH
17	10C103	SITE GRADING AND DRAINAGE PLAN - NORTH
18	10C104	SITE GRADING AND DRAINAGE PLAN - SOUTH
19	10S105	STORM WATER POLLUTION PREVENTION PLAN (SWPPP) - NORTH
20	10C106	STORM WATER POLLUTION PREVENTION PLAN (SWPPP) - SOUTH
21	10C107	POST CONSTRUCTION STORM MANAGEMENT PLAN
22	10L101	SITE LANDSCAPE PLAN
23	10L501	LANDSCAPE DETAILS
24	10D101	SITE PIPING PLAN
25	10E101	SITE ELECTRICAL PLAN

SHEET	FILE	(20) - COMPOSITE ELEVATED STORAGE TANK (BASE BID)
26	20U101	STRUCTURAL AND PROCESS - PLANS
27	20U301	STRUCTURAL AND PROCESS - SECTION AND ELEVATION
28	20E101	ELECTRICAL PLAN AND SECTION
29	20E601	ONE LINE DIAGRAM AND SCHEDULE

SHEET	FILE	(21) - HYDROPILLAR ELEVATED STORAGE TANK (BID ALTERNATE NO. 1)
30	21U101	STRUCTURAL AND PROCESS - PLANS
31	21U301	STRUCTURAL AND PROCESS - SECTION AND ELEVATION
32	21E101	ELECTRICAL PLAN AND SECTION

SHEET	FILE	(30) - BULK WATER SALES STATION
33	30U101	FOUNDATION PLAN, SECTIONS & DETAILS
34	30U102	PROCESS AND ELECTRICAL - PLANS & SECTIONS

LOCATION MAP
NOT TO SCALE



UTILITY NOTES:
VISUAL INDICATIONS OF UTILITIES ARE AS SHOWN. UNDERGROUND LOCATIONS SHOWN, AS FURNISHED BY THEIR LESSORS, ARE APPROXIMATE AND SHOULD BE VERIFIED IN THE FIELD AT THE TIME OF CONSTRUCTION. FOR ACTUAL FIELD LOCATIONS OF UNDERGROUND UTILITIES IN IOWA, CALL 1-800-292-8989.

**PRELIMINARY
NOT FOR CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN REMOVED. THIS
SHOULD NOT BE CONSIDERED A CERTIFIED DOCUMENT

03-2023

1	2	3	4	5	6	7	8
A/C AIR CONDITIONING A ARCHITECT/ENGINEER AB ANCHOR BOLT ABN ANCHOR ABC AGGREGATE BASE COURSE ABT ABOUT AC ALTERNATING CURRENT ACK ACKNOWLEDGE ACD ACQUITTIC CEILING PANEL ACST ASPHALTIC CONCRETE PAVEMENT ACST ACQUITTIC ADD ADDENDUM, AREA DRAIN ADL ADDITIONAL ADH ADHESIVE ADJ ADJUSTABLE, ADJACENT AF AMP FRAME, AMP FUSE AFF ABOVE FINISH FLOOR AGR ABOVE FINISH GRADE AGGR AGGREGATE AIC AREA INLET, ANALOG INPUT AIC AMPS INTERRUPTING CAPACITY ALG ALIGNMENT ALT ALTERNATE, ALTITUDE ALL ALUMINUM AM ACCOUTICAL MATERIAL AMB AMBIENT ANC ANCHOR AO ANALOG OUTPUT AP ACCESS PANEL APRX APPROXIMATE APVD APPROVED ARCH ARCHITECTURAL ASSY ASSEMBLY AT ACQUITTIC TILE, AMP TRIP ATC ACQUITTIC TILE CEILING ATM ATMOSPHERE AUTO AUTOMATIC AUX AUXILIARY AVE AVENUE AVG AVERAGE AWG AMERICAN WIRE GAGE AWT AMERICAN WALL TILE	CLKG CAULKING CLR CLEAR CMH COMMUNICATION MANHOLE CMP CORRUGATED METAL PIPE CMU CONCRETE MASONRY UNIT CO CLEANOUT, CONCRETE OPENING COL COLUMN COM COMMON COMB COMBINATION COMM COMMUNICATION COMP COMPOSITION, COMPRESSIBLE CON CONCRETE CONH CONNECTION CONH CONSTRUCTION CONT CONTINUOUS COOR COORDINATE CORR CORROSIVE, CORRUGATED CORR CHECKER PLATE, CONTROL POINT CPG COUPLING CPL CORROSION RESISTANT LINING CSC COMPRESSION SLEEVE COUPLING CSK COUNTERSINK CSS CLUNG SERVICE SINK CT CERAMIC TILE CTJ CONTRACTION JOINT CTR CENTER CTRL CONTROL CUT CUT CVP COPPER, CUBIC CWB CLOMBRE CY CUBIC YARD	F TO F FAB FABRICATE FB FLOOR BEAM FBD FIBERBOARD FBO FIBERGLASS FBM BOARD FOOT MEASURE FBO FURNISHED BY OWNER FC FLUSHING CONNECTION FCA FLANGED COUPLING ADAPTER FD FLOOR DRAIN FDC FLEXIBLE DUCT CONNECTION FDR FEEDER FOT FOUNDATION FE FLANGED END FEC FIRE EXTINGUISHER CABINET FES FLARED END SECTION FEXT FIRE EXTINGUISHER FF FAR FACE, FACTORY FINISH, FLAT FACE FG FINISHED GRADE FH FIRE HYDRANT FI FIGURE FIN FINISH FJT FLOW JOINT FL FLOW, FLOW LINE FLEX FLEXIBLE FLO FLANGE FLOR FLORESCENT FLR FLOOR FLS FLASHING, FLUSH FN FENCE FO FINISHED OPENING, FIBER OPTIC FOT FLAT ON BOTTOM FPC FACE OF CONCRETE, FACE OF CURB FOS FACE OF FINISH FOS FACE OF MASONRY FOT FACE OF STUDS FOT FLAT ON TOP FOT FEMALE PIPE THREAD FR FRAME FRG FIBERGLASS REINFORCED PLASTIC FRM FIRE RETARDANT TREATED MATERIAL FS FLOOR SINK, FAR SIDE DEM DEMOLITION DEP DEPRESSED DEPT DEPARTMENT DET DETAIL DI DROP INLET, DUCTILE IRON, DIGITAL INPUT DI DUCTILE IRON PIPE DIA DIAMETER DIAG DIAGONAL, DIAGRAM DIF DIFFERENCE DIM DIMENSION DISCH DISCHARGE DIST DISTANCE, DISTRIBUTION DIV DIVISION DLD DEAD LOAD DMJ DOUBLE MECHANICAL JOINT DMF DOUBLE PROOFING DN DOWN DO DISSOLVED OXYGEN, DIGITAL OUTPUT, DITTO DO DEPTH DPOT DOUBLE POLE, DOUBLE THROW DPST DOUBLE POLE, SINGLE THROW DS DOWN SPOUT GJ GROUDED TIE, DRIP TRAP ASSEMBLY DUP DUPLICATE DWA DRAWING DNL DOWEL DWR DRAWER	FACE TO FACE FACE AND BYPASS FAB FABRICATE FB FLOOR BEAM FBD FIBERBOARD FBO FIBERGLASS FBM BOARD FOOT MEASURE FBO FURNISHED BY OWNER FC FLUSHING CONNECTION FCA FLANGED COUPLING ADAPTER FD FLOOR DRAIN FDC FLEXIBLE DUCT CONNECTION FDR FEEDER FOT FOUNDATION FE FLANGED END FEC FIRE EXTINGUISHER CABINET FES FLARED END SECTION FEXT FIRE EXTINGUISHER FF FAR FACE, FACTORY FINISH, FLAT FACE FG FINISHED GRADE FH FIRE HYDRANT FI FIGURE FIN FINISH FJT FLOW JOINT FL FLOW, FLOW LINE FLEX FLEXIBLE FLO FLANGE FLOR FLORESCENT FLR FLOOR FLS FLASHING, FLUSH FN FENCE FO FINISHED OPENING, FIBER OPTIC FOT FLAT ON BOTTOM FPC FACE OF CONCRETE, FACE OF CURB FOS FACE OF FINISH FOS FACE OF MASONRY FOT FACE OF STUDS FOT FLAT ON TOP FOT FEMALE PIPE THREAD FR FRAME FRG FIBERGLASS REINFORCED PLASTIC FRM FIRE RETARDANT TREATED MATERIAL FS FLOOR SINK, FAR SIDE DEM DEMOLITION DEP DEPRESSED DEPT DEPARTMENT DET DETAIL DI DROP INLET, DUCTILE IRON, DIGITAL INPUT DI DUCTILE IRON PIPE DIA DIAMETER DIAG DIAGONAL, DIAGRAM DIF DIFFERENCE DIM DIMENSION DISCH DISCHARGE DIST DISTANCE, DISTRIBUTION DIV DIVISION DLD DEAD LOAD DMJ DOUBLE MECHANICAL JOINT DMF DOUBLE PROOFING DN DOWN DO DISSOLVED OXYGEN, DIGITAL OUTPUT, DITTO DO DEPTH DPOT DOUBLE POLE, DOUBLE THROW DPST DOUBLE POLE, SINGLE THROW DS DOWN SPOUT GJ GROUDED TIE, DRIP TRAP ASSEMBLY DUP DUPLICATE DWA DRAWING DNL DOWEL DWR DRAWER	ID INSIDE DIAMETER, INTERIOR DIMENSION IE INVERT ELEVATION, FOR EXAMPLE IF INFLUENT IMP IMPACT INCH INCH INC INCLUDE, INCANDESCENT INF INFLUENT INSTR INSTRUMENTATION INSUL INSULATION INT INTERIOR, INTERSECTION INTERMEDIATE, INTERIOR INW INVERT IPS IRON PIPE SIZE IPT INTERNAL PIPE THREAD IR INSIDE RADIUS, IRON ROD IRR IRRIGATION ISO ISOMETRIC J BOX JB JUNCTION BOX JCT JUNCTION JFI JOINT FILLER JST JOINT JST JOINT K KIP KB KNEE BRACE KBL THOUSAND CIRCULAR MILS KO KNOCK DOWN KO KNOCK OUT KSI KIPS PER SQUARE INCH KW KILOWATT L ANGLE, LENGTH, LAVATORY, LINTEL LAD LADDER LAD LATERAL LBS LBS BOLT, POUND LBS LIQUID CHALK AND TACK BOARD LBS LANDING LBS LEADER LE LIFTING EYE LF LINEAR FOOT LNG LONG LH LEFT HAND LH LINEAR LH LIQUID LH LONG LED HORIZONTAL LH LONG LED VERTICAL LH LIQUID MARKER LECTURE UNIT LH LONGITUDINAL LH LOCAL LH LOW POINT LPS LOW-PRESSURE SODIUM LPS LIGHT LPH LEFT LPH PHASE LPH POINT OF INTERSECTION LPH PACKAGE LPH PLATE, PROPERTY LINE, PRECAST LINTEL LPH PLASTER LPH PLATFORM LPH PLUMBING LPH PLF POUNDS PER LINEAR FOOT LPH PNEU PNEUMATIC LPH POLISH LPH POS POSITIVE, POSITION LPH POLYPROPYLENE, POWER POLE LPH POINT OF REVERSE CURVATURE LPH PREFAB PREFABRICATED LPH PRELIM PRELIMINARY LPH PREP PREPARE LPH PRESS PRESSURE LPH PRI PRIMARY LPH PROP PROPER LPH PROT PROTECTION LPH PS PIPE SUPPORT LPH PSF POUNDS PER SQUARE FOOT LPH PSI POUNDS PER SQUARE INCH LPH PSIA POUNDS PER SQUARE INCH ABSOLUTE LPH PSIG POUNDS PER SQUARE INCH GAGE LPH PST PRESTRESSED LPH PT PARTITION LPH PTN PARTITION LPH PVC POLYVINYL CHLORIDE, POINT OF VERTICAL CURVE LPH PMVT PAVEMENT LPH PLYWOOD PLYWOOD LPH PWJ PLYWOOD WEB JOINT LPH PZ PIEZOMETER Q RATE OF FLOW QT QUARTY TILE QU QUARTY QTY QUANTITY QAL QUALITY	N NORTH, NEUTRAL NA NOT APPLICABLE NAT NATURAL, NATIONAL NC NORMALLY CLOSED NEG NEGATIVE NEARBY, NON-FUSED NIC NOT IN CONTRACT NO NORMALLY OPEN, NUMBER NOM NOMINAL NPS NOMINAL PIPE NPT NATIONAL PIPE THREAD NS NEAR SIDE NTS NOT TO SCALE NWL NORMAL WATER LEVEL O TO O O OUT TO OUT O OUTSIDE AIR, OVERALL ON ON CENTER OCC OVER CURRENT PROTECTION DEVICE OCC OVER CURRENT OED OPEN END DUCT OED OUTSIDE FACE, OFFICE FURNISHING OFCI OWNER FURNISHED CONTRACTOR OFCI INSTALLED OFCI OWNER FURNISHED OWNER INSTALLED OFCI ORIGINAL GROUND OH OVERHEAD OPNS OPENING OPP OPPOSITE OPT OPTIONAL OR OUTSIDE RADIUS ORD OVERFLOW ROOF DRAIN OR RIGHT-OF-WAY OVL OVERFLOW OVRH OVERHANG OVRH OBSERVATION WELL OVRH OUNCE P PAINT PA PUBLIC ADDRESS PAP PAPER PB PANIC BAR, PULL BOX PBD PARTICLE BOARD PC POINT OF CURVE, PIECE, PRECAST PCC POINT OF COMPOUND CURVATURE PCF POUNDS PER CUBIC FOOT PCT SCHEDULE PE PLAIN END PED PEDESTAL PEN PENETRATION PERF PERFORATED PERM PERMANENT PERP PERPENDICULAR PF POWER FACTOR PFU PREFABRICATED MASONRY UNIT PH PHASE PI POINT OF INTERSECTION PKG PACKAGE PL PLATE, PROPERTY LINE, PRECAST LINTEL PLAS PLASTER PLAT PLATFORM PLB PLUMBING PLF POUNDS PER LINEAR FOOT PNEU PNEUMATIC POLISH POS POSITIVE, POSITION POLYPROPYLENE, POWER POLE POINT OF REVERSE CURVATURE PREFAB PREFABRICATED PRELIM PRELIMINARY PREP PREPARE PRESS PRESSURE PRI PRIMARY PROP PROPER PROT PROTECTION PS PIPE SUPPORT PSF POUNDS PER SQUARE FOOT PSI POUNDS PER SQUARE INCH PSIA POUNDS PER SQUARE INCH ABSOLUTE PSIG POUNDS PER SQUARE INCH GAGE PST PRESTRESSED PT PARTITION PTN PARTITION PVC POLYVINYL CHLORIDE, POINT OF VERTICAL CURVE PMVT PAVEMENT PLYWOOD PLYWOOD PWJ PLYWOOD WEB JOINT PZ PIEZOMETER Q RATE OF FLOW QT QUARTY TILE QU QUARTY QTY QUANTITY QAL QUALITY	R&R REMOVE AND REPLACE R&R RADIUS, REGISTER, RISER RA RETURN AIR RB REBILITATE BASE, ROCK BERM RCPT ROOF DRAIN REC RECESS RECD RECEIVED RECT RECTANGULAR RED REDUCER REF REFERENCE REINF REINFORCING REIN REMOVE REIN REQUIRED REIN REBILITATE REIN RETURN REV REVISION, REVERSE RESIL RESILIENT FLOORING RFG ROOFING RFL REFLECTED, REFLECTOR RHS ROUGH RGS ROUGH GALVANIZED STEEL RGS-PVC PVC COATED RGS RH RELIEF HOOD, RIGHT HAND, RELATIVE HUMIDITY RH RESTRAINED JOINT RL REQUIRED LAP RLA RELIEF AIR RND ROUND RNO RUNNING RO ROUGH OPENING ROR RIGHT-OF-WAY RPM REVOLUTIONS PER MINUTE RR RAILROAD RSP RESILIENT VINYL TILE RVT READY S SOUTH, SINK SA SUPPLY AIR SAM SOUND-ABSORBING MASONRY UNIT SAN SANITARY SB SPLASH BLOCK SC SOLID CORE SCH SCHEDULE SCHEM SCHEMATIC SCN SCREED SE STEEL/ALUMINUM EDGE SEP SECONDARY, SECONDS SECT SECTION SEP SEPARATE SF SQUARE FOOT, SILT FENCE SHEET GLASS, SEALANT GROOVE SH SHOWER SHI SHEET SHG SHEATHING SIL SILT SIMILAR SJ SLAB JOINT SL SLOPE, STEEL LINTEL SLD SLOTTED SLS SLEEVE SMLS SEAMLESS SLAB ON GRADE SP SOUNDPROOF, STANDPIPE SPACING SPECIFICATION SPLY SUPPLY SPLY SINGLE POLE SINGLE THROW SPT SET POINT SQ SQUARE SR SHORT RADIUS SS STAINLESS STEEL ST STATION STD STANDARD STF STIFFENER STR STIRRUP STL STEEL STOR STORAGE STR STRUCTURAL, STRAIGHT SUB SUBSTITUTE SUC SUCTION SUSP SUSPENDED SUSP SQUARE YARD SYM SYMMETRICAL SYM SYMBOL SYM SYMMETRIC SYN SYNTHETIC SYS SYSTEM TAB TOP AND BOTTOM TAG TONGUE AND GROOVE TAG TILE, TREAD T TAIL ACCESSORY, TEMPERED AIR TA TANGENT TBM TEMPORARY BENCHMARK TBM TEMPORARY CONSTRUCTION EASEMENT TEF TROWEL EPOXY FLOORING TEMP TEMPORARY, TEMPERATURE THD THREAD THK THICK THRESH THRESHOLD TKSD TACK BOARD	TOB TOP OF BOLT, TOP OF BANK TOC TOP OF BEAM, TOP OF BERM TOD TOP OF CURB, TOP OF CONCRETE TOD TOP OF DUCT TOP TOP OF FOOTING TOP TOP OF PLATING TOL TOLERANCE, TOP OF LEDGER TOM TOP OF MASONRY TOP TOP OF PLATING TOPO TOPOGRAPHY TOS TOP OF SLAB, TOP OF STEEL TOS TOP OF SLOPE TOW TOP OF WALL TP TOILET PARTITION, TELEPHONE POLE, TOP OF PLATE, TRAP PRIMER TPD TOILET PAPER DISPENSER TPS TOPPING, THROUGH PLATE GIRDER TR TRANSOM TRANS TRANSITION TRENCH TRENCH DRAIN TYP TYPICAL U URINAL UG UNDERGROUND ULT ULTIMATE UNFN UNFINISHED UNO UNLESS NOTED OTHERWISE UTL UTILITY V VENT, VELOCITY, VOLT VOL VOLUME VAC VACUUM VAR VARIABLE VAP VOLT AMPERES REACTIVE VAP VAPOR BARRIER, VINYL BASE, VALVE BOX VBC VERTICAL CENTERLINE VCP VITRIFIED CLAY PIPE VCT VERTICAL CENTERLINE VEL VELOCITY VENT VENTILATION VERT VERTICAL VIB VIBRATION VGR VERTICAL GRAIN VGR VERIFY IN FIELD VNL VOLUME VPC VERTICAL POINT OF CURVATURE VPC VERTICAL POINT OF INTERSECTION VPT VERTICAL POINT OF TANGENCY VPT VERSUS, VAPOR SEAL VTR VENT THROUGH ROOF VWC VINYL WALL COVERING W WITH WO WITHOUT WATT, WEST, WIDE, WINDOW, WIRE, WOOD BASE WB WOOD BASE WC WATER CLOSET, WATER COLUMN WD WOOD, WIDTH WF WIDE FLANGE, WASH FOUNTAIN WG WIRE GLASS, WATER GAGE WH WALL HYDRANT, WEEP HOLE WHD WOOD WL WATER LEVEL WLD WELDED WM WIRE MESH WH WEATHERPROOF WTP WATERTOP, WATER SURFACE WBC WAINSCOT WT WEIGHT, WATER TIGHT WTP WATERTOP, WORKING POINT WWF WELDED WIRE FABRIC XP EXPLOSION-PROOF XSCT CROSS SECTION XXS DOUBLE EXTRA STRONG YH YARD HYDRANT YS YIELD STRENGTH

- GENERAL NOTES:**
- THESE ABBREVIATIONS APPLY TO THE ENTIRE SET OF CONTRACT DRAWINGS.
 - LISTING OF ABBREVIATIONS DOES NOT IMPLY THAT ALL ABBREVIATIONS ARE USED IN THE CONTRACT DRAWINGS.
 - ABBREVIATIONS SHOWN ON THIS SHEET INCLUDE VARIATIONS OF A WORD, FOR EXAMPLE, "MOD" MAY MEAN MODIFY OR MODIFICATION; "INC" MAY MEAN INCLUDE OR INCLUDING AND "REIN" MAY MEAN EITHER REINFORCE OR REINFORCING.
 - SEE INSTRUMENTATION LEGEND SHEET FOR PROJECT-SPECIFIC EQUIPMENT SYMBOLS, EQUIPMENT ABBREVIATIONS, AND PIPING SYSTEM ABBREVIATIONS.

000001.dwg
10/26/2023 10:47 AM
KAYHILL P&H



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940


ISSUE	DATE	DESCRIPTION
4	03-19-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-31-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER R. BAKER	
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER 10345779	

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




**CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK**

**GENERAL
ABBREVIATIONS**




FILENAME 000001.dwg
SCALE NONE
SHEET 000001

00GG002.dwg
3/14/2023 8:47 AM
Keyhill, Pat





02C501.dwg
7/15/2023 11:47 AM
Keyfile Plot



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023



CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

STANDARD DETAILS
SITE DETAILS

FILENAME 02C501.dwg
SCALE AS NOTED

SHEET
02C501

02S001.dwg
7/15/2023 1:47 PM
Kynell P.H.



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779



CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

STANDARD DETAILS
STRUCTURAL NOTES



FILENAME 02S001.dwg
SCALE AS NOTED

SHEET
02S001

GENERAL STRUCTURAL NOTES (GSN)

GENERAL

G1. SCOPE

THE NOTES ON THIS SHEET AND THE STANDARD STRUCTURAL DETAILS ARE GENERAL AND APPLY TO THE ENTIRE PROJECT WHETHER SPECIFICALLY CALLED OUT OR NOT, EXCEPT WHERE THERE ARE SPECIFIC INDICATIONS TO THE CONTRARY ON STRUCTURAL SHEETS. IF THERE ARE QUESTIONS, THEY SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER AND ANSWERED IN WRITING PRIOR TO CONSTRUCTION.

G2. APPLICABLE SPECIFICATIONS AND CODES

A. INTERNATIONAL BUILDING CODE (IBC) 2021 EDITION AS PROMULGATED BY INTERNATIONAL CODE COUNCIL, FALLS CHURCH VIRGINIA, AS AMENDED BY THE CITY OF ANKENY, IA, UNO.
B. ASCE 7

G3. DESIGN CRITERIA

APPLIES TO ALL STRUCTURES (UNO)

1. DEAD LOAD:

1.1. ACTUAL TRIBUTARY STRUCTURE WEIGHT

2. LIVE LOAD:

2.1. WALKWAYS, STAIRS, GRATING: 100 PSF

2.2. SLAB ON GRADE: 250 PSF

3. WIND: (ASCE 7-16 BASIS)

3.1. RISK CATEGORY: IV

3.2. BASIC WIND SPEED: 122 MPH

3.3. EXPOSURE: C

4. SEISMIC

4.1. ALL STRUCTURES

4.1.1. RISK CATEGORY: IV

4.1.2. IMPORTANCE FACTOR: 1.50

4.1.3. SPECTRAL RESPONSE ACCELERATION, SS: 0.05

4.1.4. SPECTRAL RESPONSE ACCELERATION, S1: 0.05

4.1.1. SITE CLASS: D

4.1.2. SEDMAC DESIGN CATEGORY: A

4.1.3. SPECTRAL RESPONSE COEFFICIENT, SDS: 0.064

4.1.4. SPECTRAL RESPONSE COEFFICIENT, SD1: 0.091

5. SNOW LOAD:

5.1. GROUND SNOW LOAD: 30 PSF

5.2. IMPORTANCE FACTOR: 1.20

6. FLOOD CRITERIA:

6.1. FLOOD ELEVATION: 911.00 FT

G4. THE FOLLOWING NON-CONTRACTUAL GEOTECHNICAL REPORT WAS DEVELOPED FOR THIS PROJECT AND IS THE BASIS OF THE STRUCTURAL DESIGN:

GEOTECHNICAL FIRM NAME: TERRACON CONSULTANTS, INC.
ADDRESS: 600 SW 7TH ST, SUITE M, DES MOINES IA 50309
REPORT NUMBER: 08225107-03
REPORT DATE: SEPTEMBER 23, 2022

EQUIPMENT PADS AND FOUNDATIONS FOR INCIDENTAL STRUCTURES:
NET ALLOWABLE SOIL BEARING PRESSURE: 2000 PSF

G5. SAFETY

SAFETY AND STRUCTURE STABILITY DURING CONSTRUCTION ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. STRUCTURES HAVE BEEN DESIGNED TO RESIST THE DESIGN LIVE LOADS ONLY AS A COMPLETED STRUCTURE.

G6. DO NOT BACKFILL AGAINST WALLS PRIOR TO GROUND LEVEL CONCRETE FRAMING AND SLAB HAVE REACHED THEIR 28-DAY CONCRETE DESIGN STRENGTH.

G7. OPENINGS

OPENINGS FOR PIPES, DUCTS, CONDUITS, ETC. ARE NOT ALL SHOWN ON THE STRUCTURAL DRAWINGS. COORDINATE AND PROVIDE OPENINGS AS REQUIRED TO ACCOMMODATE ALL WORK SHOWN OR SPECIFIED IN THE CONTRACT DOCUMENTS AND

OTHERWISE REQUIRED FOR THE FURNISHING OF A FUNCTIONALLY COMPLETE PROJECT. REINFORCE AROUND OPENINGS PER STANDARD STRUCTURAL DETAILS UNLESS OTHERWISE SHOWN.

G8. SPECIAL STRUCTURAL INSPECTION SHALL BE PERFORMED AS REQUIRED BY OWNER.

G9. STANDARD DETAILS

THE STANDARD DETAILS DEPICT TYPICAL DETAILING TO BE USED ON THIS PROJECT. IF CONDITIONS ARE NOT EXPLICITLY SHOWN ON THE DRAWINGS THEY SHALL BE MADE SIMILAR TO THE STANDARD DETAILS. OBTAIN APPROVAL OF ENGINEER IN WRITING FOR SIMILAR CONDITIONS PRIOR TO CONSTRUCTION.

G10. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND ELEVATIONS OF EXISTING CONSTRUCTION AS REQUIRED TO COORDINATE NEW CONSTRUCTION. SUBMIT REQUIRED CHANGES FOR APPROVAL.

G11. CONTRACTOR TO SUBMIT FOR REVIEW ALL EQUIPMENT SIZES, OPERATING WEIGHTS, VIBRATION FORCES, SUPPORT LOCATIONS, ALONG WITH ANY FLOOR OPENINGS, NOTCHES, AND RECESSES REQUIRED BY SUCH EQUIPMENT. CONCRETE SUPPORT PADS AND/OR FRAMING REQUIRED TO SUPPORT SAID EQUIPMENT SHALL NOT BE FABRICATED AND PLACED UNTIL THE CONCRETE SUPPORT PADS AND/OR FRAMING IS APPROVED TO SUPPORT THE EQUIPMENT.

G12. VOIDS MAY NOT BE FORMED BY MEANS OF FILLING CAVITY WITH MATERIAL. FORM MATERIALS MAY BE LEFT IN PLACE.

CONCRETE

C1. DESIGN FOR EXTERIOR FOUNDATIONS:

CONCRETE

F_c = 4500 PSI

REINFORCING

F_y = 60000 PSI

C2. CONCRETE COVER

UNLESS OTHERWISE NOTED, PROVIDE CONCRETE COVER FOR REINFORCING AS FOLLOWS:

CONCRETE DEPOSITED AGAINST EARTH: 3"

ALL OTHER: 2"

SEE DRAWINGS FOR EXCEPTIONS

C3. SEE SPECIFICATIONS FOR REINFORCING PLACEMENT REQUIREMENTS.

C4. REFER TO OTHER DISCIPLINE DRAWINGS PRIOR TO CONSTRUCTION FOR EMBEDDED ITEMS AND PENETRATIONS NOT SHOWN ON STRUCTURAL DRAWINGS. AS REQUIRED TO ACCOMMODATE ALL WORK SHOWN OR SPECIFIED IN THE CONTRACT DOCUMENTS AND OTHERWISE REQUIRED FOR THE FURNISHING OF A FUNCTIONALLY COMPLETE PROJECT. REINFORCE AROUND OPENINGS PER STANDARD STRUCTURAL DETAILS UNLESS OTHERWISE SHOWN.

C5. PROVIDE 3/4" CHAMFERS AT ALL EXPOSED EDGES AND 1/2" CHAMFERS AT JOINTS AS SHOWN. NOT ALL CHAMFERS MAY BE SHOWN ON DRAWINGS.

C6. FIELD ADJUST REINFORCING AT OPENINGS AND EMBEDDED ITEMS AS INDICATED.

C7. CONTINUOUS WATERSTOP SHALL BE INSTALLED IN JOINTS SUBJECT TO STATIC WATER PRESSURE.

C8. ABSOLUTELY NO WELDING OF REINFORCING BARS OR TORCHING TO BEND REINFORCING BARS SHALL BE ALLOWED WITHOUT SPECIFIC APPROVAL FROM THE STRUCTURAL ENGINEER.

C9. CONTRACTOR SHALL SUBMIT A CONCRETE PLACEMENT PLAN IDENTIFYING JOINT TYPES, JOINT LOCATIONS AND CONCRETE PLACEMENT SEQUENCE.

C10. ALL CAST IN PLACE AND POST-INSTALLED ANCHORS INDICATED IN THE STRUCTURAL DOCUMENTS SHALL COMPLY WITH APPENDIX D OF ACI 318 AND CHAPTER 19 OF THE IBC. ALL EXPANSION AND ADHESIVE ANCHORS SHALL HAVE THE ICC REPORT SHOWING EQUIVALENT LOAD CAPACITY. SUBMIT AND INSTALL PER THE ICC EVALUATION REPORT.

C11. UNLESS OTHERWISE SHOWN, SPLICES FOR BOTTOM REINFORCING BARS IN BEAMS AND SLABS SHALL BE CENTERED OVER THE SUPPORTS. SPLICES FOR TOP REINFORCING BARS SHALL BE LOCATED ON CENTERLINE OF SPAN.


C12. ALL REINFORCING SHALL BE CONTINUOUS THROUGH CONSTRUCTION JOINTS UNLESS NOTED OTHERWISE.

C13. ALL BARS INDICATED AS BEING HOOKED SHALL HAVE ACI STANDARD 90 DEGREE OR 180 DEGREE HOOKS AS SHOWN.

POST-INSTALLED ANCHORS

PA1. POST-INSTALLED ANCHORS SHALL ONLY BE USED WHERE SPECIFIED ON THE CONTRACT DRAWINGS. THE CONTRACTOR SHALL OBTAIN APPROVAL FROM THE ENGINEER OF RECORD (EOR) PRIOR TO INSTALLING POST-INSTALLED ANCHORS FOR MISSING OR MISPLACED CAST-IN-PLACE ANCHORS.

PA2. CARE SHALL BE TAKEN IN PLACING POST-INSTALLED ANCHORS TO AVOID CONFLICTS WITH EXISTING REBAR. HOLES SHALL BE DRILLED AND CLEANED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS.



NOTES:

1. PROVIDE ADDITIONAL REINFORCING THE SAME SIZE AS DISCONTINUOUS REINFORCEMENT AT OPENING. QUANTITY OF REINFORCING IN EACH DIRECTION SHALL BE EQUAL TO OR ONE GREATER THAN THE NUMBER OF DISCONTINUOUS BARS. PLACE 1/2 OF ADDITIONAL REINFORCING BARS EACH SIDE OF OPENING. PLACE ADDITIONAL REINFORCEMENT AT 3" OC (TYPICAL BOTH DIRECTIONS AND ALL LAYERS OF REINFORCEMENT). START FIRST BAR 2" CLEAR TO OPENING.
2. EXTEND ADDITIONAL REINFORCING BEYOND EDGE OF OPENING AS SHOWN. ADDITIONAL BARS MAY TERMINATE AT THE END OF THE WALL WITH A STANDARD HOOK WHERE THE LENGTH OF THE WALL WILL NOT PERMIT BARS TO EXTEND AS SHOWN.
3. TYPICAL WALL OR SLAB REINFORCING NOT SHOWN FOR CLARITY. TERMINATE TYPICAL REINFORCING 2" CLEAR TO OPENING.
4. OPENINGS 12" OR LESS IN SLABS AND OPENINGS 12" OR LESS IN WALLS. NO ADDITIONAL REINFORCING REQUIRED, UNLESS SHOWN OTHERWISE. TYPICAL REINFORCING SHALL BE RESPALED (NOT CUT) TO ALLOW FOR OPENINGS TO BE MADE.
5. UNLESS SHOWN OTHERWISE ON DRAWINGS, PROVIDE EXTRA REINFORCING AROUND OPENINGS AS SHOWN AND INDICATED ABOVE.
6. PROVIDE ADDITIONAL DOWELS PER NOTE 1 ABOVE FOR ALL OPENINGS NEAR THE FLOOR SLAB, BASE SLAB, OR CORNERS.

EXTRA REINFORCING AROUND OPENINGS

NOT TO SCALE


BAR	MIN BAR SPACING	MINIMUM LAP SPICE LENGTHS $f'_c = 4500$ PSI			
		LAPS FOR BARS SPACED GREATER THAN MIN BAR SPACING		LAPS FOR BARS SPACED CLOSER THAN MIN BAR SPACING	
		VERTICAL	OTHER	VERTICAL	OTHER
#3	3"	1'-4"	1'-6"	1'-4"	1'-6"
#4	3"	1'-7"	2'-0"	1'-8"	2'-2"
#5	3"	1'-11"	2'-6"	2'-2"	3'-4"
#6	4"	2'-4"	3'-0"	3'-8"	4'-9"
#7	4"	3'-6"	4'-8"	4'-11"	6'-5"
#8	4"	4'-7"	5'-11"	6'-8"	8'-6"
#9	4 1/2"	5'-9"	7'-6"	8'-3"	10'-9"
#10	5"	7'-4"	9'-8"	10'-6"	13'-7"
#11	5 5/8"	9'-0"	11'-8"	12'-10"	16'-8"

NOTES:

1. ALL REBAR SPICE LENGTHS SHALL BE AS SHOWN UNDER HEADING "VERTICAL" EXCEPT IF SPICED BARS ARE HORIZONTAL BARS WITH 12" OR MORE CONCRETE BELOW. THEN SPICE LENGTH SHALL BE AS SHOWN UNDER HEADING "OTHER".
2. AT SPICES THE BAR SPACING IS THE CENTER TO CENTER DISTANCE BETWEEN ADJACENT REBARS.
3. ALL SPICES SHALL BE CONTACT SPICES AND WIRED TOGETHER.
4. NO WELDED OR MECHANICAL SPICES ARE PERMITTED UNLESS INDICATED OTHERWISE.
5. UNLESS OTHERWISE SHOWN, SPICES FOR BOTTOM REINFORCING BARS IN BEAMS AND SLABS SHALL BE CENTERED OVER THE SUPPORTS. SPICES FOR TOP REINFORCING BARS SHALL BE LOCATED ON CENTERLINE OF SPAN.

CONCRETE REINFORCING LAP SPICE SCHEDULE

NOT TO SCALE




NOTES:

1. ALL HOOKS SHALL BE STD 90 DEGREE HOOKS.
2. SEE DRAWINGS FOR ADDITIONAL HORIZONTAL BAR STAGGER BETWEEN TYPICAL REINFORCING. EXTEND TO 1/5 OF DISTANCE TO NEAREST ADJACENT WALL IN EACH DIRECTION, UNO.
3. OPTIONAL LAP LOCATION, APPLIES TO BOTH DOUBLE AND SINGLE LAYER CONDITIONS TYP.

WALL REINFORCEMENT AT CORNERS AND INTERSECTIONS

NOT TO SCALE




NOTES:

1. CORNER BARS TO BE SAME SIZE AND SPACING AS FOOTING REINFORCING.

TYPICAL EXTERIOR EQUIPMENT PAD

NOT TO SCALE



NOTES:

1. INCREASE SLAB THICKNESS AS REQUIRED TO MAINTAIN MIN 3" CONCRETE COVER BELOW EQUIPMENT ANCHOR BOLTS.
2. AT CONTRACTOR'S OPTION, REPLACE GRANULAR FILL W/CONCRETE POURED WITH PERIMETER GRADE BEAM AND TOP SLAB. PROVIDE ALL REINFORCING SHOWN IN SECTION.
3. PROVIDE OPENINGS AS REQD FOR PENETRATIONS. REINFORCE AROUND OPENINGS PER DETAIL 1/025501.

TYPICAL EXTERIOR EQUIPMENT PAD

NOT TO SCALE

BAR SIZE	HL	HW	TL	D	$f'_c = 4.0$ OR 4.5 KSI
GRADE 60					Ldh *
#3	6"	3"	3"	2 1/4"	6"
#4	8"	4"	4 1/2"	3"	7"
#5	10"	5"	5"	3 3/4"	9"
#6	1'-0"	6"	6"	4 1/2"	10"
#7	1'-2"	7"	7"	5 1/4"	12"
#8	1'-4"	8"	8"	6"	14"
#9	1'-7"	11 3/4"	10 1/2"	9 1/2"	15"
#10	1'-10"	1'-1 1/4"	11 1/2"	10 3/4"	17"
#11	2'-0"	1'-2 3/4"	1'-1"	12"	19"



* COMPLYING WITH MINIMUM COVER REQUIREMENTS OF ACI 318, 12.5.3. OTHERWISE Ldh MUST BE RE-CALCULATED.

REINFORCING HOOK SCHEDULE

NOT TO SCALE

LUMP SUM RETAINING WALL WORK:

PAYMENT WILL BE MADE AT THE LUMP SUM PRICE FOR COMPLETE RETAINING WALL. LUMP SUM PRICE INCLUDES, BUT IS NOT LIMITED TO, EXCAVATION OF NATIVE MATERIALS FOR RETAINING WALL CONSTRUCTION; SUBGRADE PREPARATION; FURNISHING AND INSTALLING REINFORCING STEEL; FURNISHING, PLACING, AND CURING CONCRETE; FURNISHING AND INSTALLING GRANULAR FILL, DRAINAGE MATERIAL AND FILTER FABRIC; AND BACKFILLING WITH COMPACTED NATIVE MATERIAL.



RETAINING WALL DETAIL


NOT TO SCALE

PROJECT MANAGER R. BAKER			CIVIL G. NORTON		
PROCESS R. BAKER			STRUCTURAL D. WISEMAN		
			ELECTRICAL K. BOYD		
4	03-10-2023	100% REVIEW SET			
3	02-08-2023	90% INTERNAL REVIEW SET			
2	12-21-2022	90% CLIENT REVIEW SET			
1	09-08-2022	50% REVIEW SET			
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER 10345779		

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023



**CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK**

**STANDARD DETAILS
TYPICAL CONCRETE DETAILS**

FILENAME 025501.dwg
SCALE AS NOTED

SHEET

02S501

02D501.dwg
3/15/2023 10:43 AM
Keyfile Plot



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-06-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	O. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK




FILENAME 02D501.dwg
SCALE AS NOTED

SHEET
02D501





- NOTES:**
1. USE DUCTILE IRON PIPE WITH RESTRAINED MECHANICAL JOINTS FOR FIRE HYDRANT ASSEMBLY AND ANCHOR TEE.
 2. SEE THE CONTRACT DOCUMENTS FOR THE LOCATION OF EACH HYDRANT AND THE LENGTH OF ANCHORING PIPE.



1 LARGE DIAMETER HYDRANT ASSEMBLY DETAILS
NOT TO SCALE

KEY
OD= OUTSIDE DIAMETER OF PIPE
TW= TRENCH WIDTH AT TOP OF PIPE:
MIN. = OD+18 INCHES OR 1.25XOD+12 INCHES (WHICHEVER IS GREATER)
D= DEPTH OF BEDDING MATERIAL BELOW PIPE:
MIN. = OD/8 OR 4 INCHES (WHICHEVER IS GREATER)



BEDDING CLASSES
ALLOWABLE BURY DEPTH

**DUCTILE IRON, AWWA
C151, CLASS 52**


PIPE DIAMETER (INCHES)	CLASS P-1 BEDDING	CLASS P-2 BEDDING	CLASS P-3 BEDDING
4	40'	40'	40'
6	40'	40'	40'
8	40'	40'	40'
10	36'	40'	40'
12	31'	40'	40'
14	26'	40'	40'
16	23'	37'	40'
18	20'	34'	40'
20	18'	32'	40'
24	16'	29'	36'
30	13'	23'	31'
36	13'	22'	30'
42	13'	21'	29'
48	13'	19'	27'
54	13'	19'	27'

PVC, AWWA C900, DR18


PIPE DIAMETER (INCHES)	CLASS P-1 BEDDING	CLASS P-2 BEDDING	CLASS P-3 BEDDING
4	19'	23'	40'
6	19'	23'	40'
8	19'	23'	40'
10	19'	23'	40'
12	19'	23'	40'
14	19'	23'	40'
16	19'	23'	40'
18	19'	23'	40'
20	19'	23'	40'
24	19'	23'	40'

① PLACE REMAINDER OF BEDDING AND BACKFILL MATERIAL AS SPECIFIED IN THE CONTRACT DOCUMENTS.

2 PIPE BEDDING DETAILS
NOT TO SCALE




ELEVATION




SECTION A-A

CHANGES IN PIPE DEPTH




PLAN

NOTE:
1. USE ONLY WHEN ALLOWED BY THE ENGINEER, OR WHEN SPECIFIED IN THE CONTRACT DOCUMENTS.



SECTION B-B


DEAD ENDS (ALTERNATE METHOD)




TYPICAL SECTION

NOTES:


1. EXTEND THRUST BLOCKS TO UNDISTURBED SOIL. EXCAVATION INTO TRENCH WALL MAY BE NECESSARY.
2. FORM VERTICAL SURFACES OF POURED CONCRETE THRUST BLOCKS EXCEPT ON BEARING SURFACE.
3. ENCASE ALL FITTINGS IN POLYETHYLENE WRAP. DO NOT ALLOW CONCRETE TO DIRECTLY CONTACT JOINTS OR FITTING BOLTS.




TEE




TEE




BEND



CROSS



CROSS



DEAD END

TYPICAL PLANS

DIAMETER OF PIPE, D (INCHES)	MINIMUM BEARING SURFACE (sq ft)				
	BENDS				TEES AND DEAD ENDS
	11 1/2'	22 1/2'	45'	90'	
4	1	1	2	4	3
6	1	2	4	8	5
8	2	4	7	14	10
10	3	6	11	21	15
12	4	8	16	29	21
14	5	11	21	39	28
16	7	14	27	50	36
18	9	17	34	63	45
20	11	21	42	78	55
24	15	31	60	111	78
30	24	47	92	171	120
36	34	67	132	244	173


MINIMUM SURFACE AREA BASED ON WATER PRESSURE OF 150 PSI AND ALLOWABLE SOIL PRESSURE OF 1,000 PSF.

1 THRUST BLOCK DETAILS

NOT TO SCALE

KEYNOTES: (1)

1. EXTEND TRACER WIRE UP FIRE HYDRANT BARREL TO INTERNAL TERMINALS OF TRACER WIRE STATION AND BACK DOWN. REFER TO SHEET 02D501 FOR DETAILS OF FIRE HYDRANT ASSEMBLY.
2. CLAMP TRACER WIRE TO GROUND ROD AT SYSTEM TERMINATION POINTS.



3 PIPE TRACER WIRE INSTALLATION DETAILS

NOT TO SCALE

2 THRUST BLOCK DETAILS

NOT TO SCALE

02D502.dwg
11/25/2023 1:43 PM
Karyn R. Post



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	O. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

PRELIMINARY
NOT FOR
CONSTRUCTION
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023



CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK


STANDARD DETAILS
WATER MAIN & APPURTENANCE DETAILS



FILENAME | 02D502.dwg
SCALE | AS NOTED

SHEET


02D502



1 ELECTRICAL EQUIPMENT RACK DETAIL
NOT TO SCALE

DETAIL NOTES:

1. SEE SHEET 20E101 FOR LOCATION OF EQUIPMENT RACK.
2. PROVIDE GROUNDING PER SHEET 20E101 AND SPECIFICATION 26 05 26.
3. MODULAR STRUT WIDTH: 1 5/8\".
4. ADD WEATHER PROTECTED (IN USE) DUPLEX RECEPTACLE TO RACK.
5. COMBINED EQUIPMENT LOADS PER 36\" SPAN SHALL NOT EXCEED 500 LBS.
6. RACK ASSEMBLY MATERIAL: STAINLESS STEEL.
7. ANCHORS: STAINLESS STEEL, 1/2\" DIAMETER, 3 1/2\" EMBEDMENT.
8. PROTECT SURFACES WITH DISSIMILAR MATERIALS.
9. REPAIR CUT ENDS AND DAMAGED SURFACES PER MANUFACTURER'S RECOMMENDATIONS.




2 TYPICAL GUARDRAIL MOUNTED YAGI ANTENNA MOUNTING DETAIL
NOT TO SCALE

NOTES:

1. PROTECT SURFACES WITH DISSIMILAR METALS WITH COMPATIBLE EPOXY COATING.
2. ANTENNAS SHALL BE MOUNTED WITH A MINIMUM 8\" SPACING FROM OTHER ANTENNAS.

DIMENSION SCHEDULE			
POLE HEIGHT	MINIMUM D	MINIMUM H	VERTICAL REBAR EACH
UP TO 10'	2'-0"	4'-6"	6
11' TO 20'	2'-0"	6'-6"	6
21' TO 30'	2'-0"	8'-6"	6
31' TO 50'	2'-0"	10'-6"	6



3 LIGHT POLE FOUNDATION
NOT TO SCALE

Revised: Blaine J.

02/20/23 2:26 PM



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

**STANDARD DETAILS
ELECTRICAL DETAILS**

FILENAME: 022023.dwg
SCALE: AS NOTED


SHEET
02E501




1
—

CONCRETE ENCASED
DUCTBANK SECTION


NOT TO SCALE



DIRECT BURIED CONDUIT(S)
SECTION
2
- NOT TO SCALE



MULTIPLE PANEL/DEVICE
MODULAR EQUIPMENT RACK



4
- TYPICAL GUARDRAIL MOUNTED
- NOT TO SCALE



5
—

CAST-IN-PLACE
ELECTRICAL HANDHOLE

NOT TO SCALE

			PROJECT MANAGER	R. BAKER
			CIVIL	G. NORTON
			PROCESS	R. BAKER
			STRUCTURAL	D. WISEMAN
			ELECTRICAL	K. BOYD
4	03-10-2023	100% REVIEW SET		
3	02-08-2023	90% INTERNAL REVIEW SET		
2	12-21-2022	90% CLIENT REVIEW SET		
1	09-08-2022	50% REVIEW SET		
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT



CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK


STANDARD DETAILS

ELECTRICAL DETAILS



FILENAME	02P5011.wg
SCALE	AS NOTED

SHEET
02E502



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
1	03-10-2023	100% REVIEW SET
2	02-08-2023	90% INTERNAL REVIEW SET
3	12-21-2022	90% CLIENT REVIEW SET
4	09-26-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINEDALE DRIVE
ELEVATED WATER
STORAGE TANK

**SITE PLANNING
EXISTING CONDITIONS AND SURVEY PLAN**

FILENAME 10V101.dwg
SCALE 1" = 20'

SHEET
10V101



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-09-2022	50% REVIEW SET
ISSUE	DATE	DESCRIPTION

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT




**CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK**

**SITE PLANNING
EXISTING CONDITIONS AND SURVEY PLAN**

FILENAME: 10v102.dwg
SCALE: 1" = 20'

SHEET
10V102




300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT



**CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK**

**SITE PLANNING
SITE LAYOUT PLAN
NORTH**

FILENAME | 10C101.dwg
SCALE | 1" = 20'

SHEET
10C101

1 2 3 4 5 6 7 8

STRUCTURE TABLE			
NAME	RIM	CONNECTED PIPES	LOCATION
AI-1	983.77	15" IN (W) = 980.54 15" OUT (S) = 980.54	N 642110.103 E 1602791.871
AI-2	983.76	15" IN (N) = 980.24 15" OUT (S) = 980.24	N 642050.175 E 1602793.416
AI-3	981.50	15" IN (E) = 975.81 15" OUT (W) = 975.71	N 642000.209 E 1602598.359
CI-1	983.59	6" IN (E) = 980.80 6" IN (W) = 980.10 6" IN (N) = 980.80 15" OUT (SE) = 980.84	N 642123.683 E 1602775.872
CI-2	985.14	6" IN (E) = 979.18 6" IN (N) = 979.65 15" OUT (E) = 979.80	N 642030.163 E 1602598.334
CI-3	982.04	15" IN (E) = 978.22 6" IN (N) = 979.80 15" OUT (W) = 978.12	N 642001.435 E 1602599.009

STRUCTURE TABLE			
NAME	RIM	CONNECTED PIPES	LOCATION
FES-1	N/A	15" IN (N) = 980.10	N 642022.142 E 1602794.391
FES-2	N/A	15" IN (W) = 979.56	N 642013.584 E 1602843.550
MH-1	982.00	15" IN (E) = 975.35	N 641988.424 E 1602533.227
OUTLET STRUCTURE	982.70	4" IN (E) = 978.50 15" OUT (W) = 978.45	N 642005.590 E 1602645.526

STRUCTURE TABLE			
NAME	RIM	CONNECTED PIPES	LOCATION
BEND-1	N/A	6" IN (E) = 979.24 6" OUT (W) = 979.24	N 642028.528 E 1602810.887
CO-1	986.10	6" OUT (W) = 982.75	N 642124.623 E 1602908.448
CO-2	984.04	6" OUT (N) = 981.54	N 642051.486 E 1602597.358
CO-3	983.07	6" OUT (S) = 980.00	N 642026.732 E 1602597.358
CO-4	985.35	6" OUT (S) = 982.41	N 642147.249 E 1602843.098
CO-5	983.82	6" OUT (W) = 979.57	N 642029.554 E 1602676.369
CO-6	985.00	6" OUT (S) = 981.46	N 642146.232 E 1602775.921
CO-7	984.33	6" OUT (S) = 980.50	N 642145.376 E 1602746.501

STRUCTURE TABLE			
NAME	RIM	CONNECTED PIPES	LOCATION
CO-8	984.81	6" OUT (S) = 981.00	N 642144.360 E 1602886.323
CO-9	984.23	6" OUT (S) = 980.28	N 642142.738 E 1602614.963
CO-10	983.44	6" OUT (E) = 980.48	N 642118.278 E 1602573.769
CO-11	983.86	6" OUT (W) = 980.25	N 642076.317 E 1602673.987
CO-BR	979.90	4" OUT (W) = 977.00	N 642012.052 E 1602851.119
TEE-1	N/A	6" IN (N) = 981.67 6" IN (E) = 981.67 6" OUT (W) = 981.67	N 642123.368 E 1602843.552
TEE-2	N/A	6" IN (S) = 980.89 6" IN (E) = 980.99 6" OUT (W) = 980.99	N 642122.711 E 1602807.027
TEE-3	N/A	6" IN (N) = 980.20 6" IN (W) = 980.20 6" OUT (E) = 980.20	N 642121.593 E 1602746.968

STRUCTURE TABLE			
NAME	RIM	CONNECTED PIPES	LOCATION
TEE-4	N/A	6" IN (N) = 980.29 6" OUT (E) = 980.29 6" OUT (W) = 980.29	N 642120.432 E 1602886.793
TEE-5	N/A	6" IN (N) = 980.00 6" IN (E) = 980.00 6" OUT (W) = 980.00	N 642119.402 E 1602615.391
TEE-6	N/A	6" IN (E) = 979.80 6" IN (W) = 979.80 6" OUT (S) = 979.80	N 642116.742 E 1602595.728
TEE-7	N/A	6" IN (E) = 979.75 6" IN (N) = 979.75 6" OUT (S) = 979.75	N 642074.865 E 1602596.539

SITE GRADING NOTES:

- SEE GENERAL NOTES ON SITE SHEET 10C101.
- MAINTAIN POSITIVE DRAINAGE AWAY FROM STRUCTURES THROUGHOUT CONSTRUCTION.
- SEE SHEET 10C105 FOR THE EROSION AND SEDIMENT CONTROL PLAN AND NOTES.
- RIPRAP SHALL MEET OR EXCEED THE REQUIREMENTS OF SDAS AND IOWA DOT (SPEC SECTION 4130). ALL RIPRAP SHALL BE PLACED ON GEOTEXTILE FABRIC (RIPRAP 160N OR APPROVED EQUAL). THE USE OF RECYCLED PCC PAVEMENT IS NOT PERMITTED ON THIS PROJECT.


LEGEND:

- EXISTING CONTOUR
- PROPOSED CONTOUR
- CASE B TYPE 1 AND CASE C TYPE 1 SUBDRAINS. SEE SDAS 4040.231.
- POND SUBDRAINAGE. FOLLOW SDAS STANDARD FOR CASE D TYPE 2 SUBDRAIN OR SIMILAR.
- BIORETENTION BASIN UNDERDRAIN LIMITS
- 6" ASPHALT PAVEMENT
- 5" P.C.C.
- 7" P.C.C.
- PERMANENT EROSION CONTROL

- BW BOTTOM OF WALL ELEVATION
- FF FINISH FLOOR GRADE
- GT TOP OF SIDEWALK
- TC TOP OF CURB
- TW TOP OF WALL

KEYNOTES:

- CONSTRUCT SINGLE OPEN THROAT INTAKE PER SDAS FIGURE 6010.507.
- CONSTRUCT 24" CIRCULAR AREA INTAKE PER SDAS FIGURE 6010.512 WITH TYPE 3B GRATE.
- CONSTRUCT PAVEMENT SUBDRAIN - CASE B, TYPE 1. SEE SDAS FIGURE 4040.231.
- CONSTRUCT PAVEMENT SUBDRAIN - CASE C, TYPE 1. SEE SDAS FIGURE 4040.231.
- CONSTRUCT CLASS D & E RIP RAP FOR PIPE OUTLET PER SDAS FIGURE 9048.111. WIDTH SHALL BE 3'.
- CONSTRUCT SUBDRAIN TYPE A-1 CLEANOUT. SEE SDAS FIGURE 4040.232.
- CONSTRUCT SUBDRAIN OUTLET WITH RODENT GUARD. SEE SDAS FIGURE 4040.233.
- CONSTRUCT RCP STORM SEWER. SEE PIPE TABLES ON THIS SHEET FOR SIZE. USE CLASS R-2 BEDDING PER SDAS FIGURE 3010.102.
- CONSTRUCT CAST-IN-PLACE RETAINING WALL. SEE SECTION 7025.01. TOP OF WALL SHALL BE STRAIGHT GRADED BETWEEN ELEVATIONS SHOWN.
- CONSTRUCT OUTLET STRUCTURE. SEE DETAIL 602C501.
- CONSTRUCT CIRCULAR STORM SEWER MANHOLE. SEE SDAS FIGURE 6010.401.
- REFER TO 10C107 BIORETENTION OUTLET DETAILS.
- FURNISH AND INSTALL ROLLED EROSION CONTROL. NORTH AMERICAN GREEN SC-150B, OR APPROVED EQUAL.



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	80% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

PRELIMINARY
NOT FOR
CONSTRUCTION
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

SITE PLANNING
SITE GRADING AND DRAINAGE PLAN
NORTH

FILENAME | 10C103.dwg
SCALE | 1" = 20'

SHEET
10C103



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-19-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	O. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




**CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINEDALE DRIVE
ELEVATED WATER
STORAGE TANK**

**SITE PLANNING
STORM WATER POLLUTION PREVENTION PLAN
(SWPPP)**

FILENAME | 10C105.dwg
SCALE | 1" = 20'

SHEET
10C105



300 E LOCUST ST. SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER R. BAKER	
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER 10345779	

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINEDALE DRIVE
ELEVATED WATER
STORAGE TANK

**SITE PLANNING
STORM WATER POLLUTION PREVENTION PLAN
(SWPPP)**




FILENAME 10C105.dwg
SCALE 1" = 20'


SHEET
10C106



A BIORETENTION BASIN CROSS-SECTION
10C107 NO SCALE



B BIORETENTION BASIN SECTION
10C107 NO SCALE



LEGEND:
--- LIMITS OF CONSTRUCTION

- KEYNOTES:**
1. BIORETENTION OUTLET, SEE DETAIL 602C501.
 2. BIORETENTION POND SUBDRAINAGE, SEE SECTION A ON THIS SHEET.

- NOTES:**
1. FILTER FABRIC MUST BE ARCHED AS SHOWN.
 2. OVERLAP OF FABRIC SHALL NOT EXCEED 6\".
 3. TOP 6\" OF SOIL SHALL BE BLENDED WITH 3\" OF COMPOST MIX (IOWA DEPARTMENT OF NATURAL RESOURCES). SUBMIT TO ENGINEER FOR REVIEW/APPROVAL PRIOR TO CONSTRUCTION.
 4. CONSTRUCT EROSION CONTROL BLANKET ON ALL SLOPES AND BOTTOM OF BASIN. (NORTH AMERICAN GREEN SC-150BN OR APPROVED EQUAL)
 5. RAINGARDEN MIXTURE SHALL BE PLANTED ON BOTTOM AND SLOPES (UP TO THE 98\" ELEVATION) OF THE BIORETENTION BASIN.

STORMWATER CALCULATIONS:

TOTAL PROPERTY AREA: 1.66 AC
TOTAL DISTURBED AREA: 1.66 AC

TREATMENT REQUIREMENTS:

REQUIRED TREATMENT VOLUME:
(1.66 AC) * 1.25 IN = 7,532 CF

STORMWATER DETENTION:

PER HYDROFLOW HYDROGRAPHS EXTENSION FOR AUTOCAD CIVIL 3D 2020, THE PRE AND POST CONSTRUCTION RUNOFF (CFS) FOR THE 5-, 10-, AND 100-YEAR STORM EVENTS USING THE SCS METHOD ARE SUMMARIZED IN THE TABLE BELOW.

DETENTION REQUIRED: 7,532 CF
DETENTION PROVIDED: 15,000 CF

	PEAK RUN OFF (CFS)		
	5-YEAR	10-YEAR	100-YEAR
PRE-DEVELOPED	1,520	2,419	6,983
POST-DEVELOPED	1,112	1,965	6,352



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-28-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINE DALE DRIVE
ELEVATED WATER
STORAGE TANK

**SITE PLANNING
POST CONSTRUCTION STORM MANAGEMENT PLAN
(PCSMP)**

FILENAME | 10C107.dwg
SCALE | 1" = 20'

SHEET
10C107

TREES	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE	ROOT	REMARKS
	GBA	2	GINKGO BLOBA "AUTUMN GOLD" TM	MAIDENHAIR TREE	2" CAL	B&B	
	LM	2	LIQUIDAMBAR STYRACIFLUA "MORAINI"	MORHANE SWEET GUM	2" CAL	B&B	
	TR	2	TLIA AMERICANA "REDMOND"	REDMOND AMERICAN LINDEN	2" CAL	B&B	
EVERGREEN TREE	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE	ROOT	REMARKS
	AC	5	ABIES CONCOLOR	WHITE FIR	6 FT MIN.	B&B	
	PA	5	PICEA ABIES	NORWAY SPRUCE	6 FT MIN.	B&B	
SHRUBS	CODE	QTY	BOTANICAL NAME	COMMON NAME	SIZE	ROOT	REMARKS
	AMI	8	ARONIA MELANOCARPA "MORTON" TM	ROGUS BEAUTY BLACK CHOKEBERRY	2 GAL	CG	5'-4" O.C.
	BP	13	BUDLEJA X "PURPLE HAZE"	LD & BEHOLDERS PURPLE HAZE BUTTERFLY BUSH	2 GAL	CG	3'-4" O.C.
	CAH	9	CLETHRA ALFOLIA "HUMMINGBIRD"	HUMMINGBIRD SUMMERSWEET	2 GAL	CG	5'-4" O.C.



- LANDSCAPE PLAN NOTES:**
1. CONTRACTOR SHALL LOCATE ALL UTILITY LINES AND STRUCTURES INCLUDING BUT NOT LIMITED TO MANHOLES, HANDPOLES, VALVES, AND HYDRANTS PRIOR TO THE START OF WORK.
 2. PLANT QUANTITIES IN PLANT SCHEDULE ARE FOR CONFORMANCE OF AND ARE NOT GUARANTEED. QUANTITIES ON PLAN WILL PREVAIL IF DISCREPANCIES OCCUR.
 3. CONTRACTOR SHALL SHOW PROOF OF DOCUMENT, SOURCE AND AGE OF PLANTS AND VARIETIES FOR ALL PLANTS WITH 21 DAYS FOLLOWING THE AWARD OF CONTRACT. TIMELY DOCUMENT OF ALL PLANT MATERIALS IS ESSENTIAL TO THE SUCCESSFUL COMPLETION AND ACCEPTANCE OF THE PROJECT.
 4. SUBSTITUTIONS SHALL ONLY BE ALLOWED WHEN THE CONTRACTOR HAS EXHAUSTED ALL SOURCES AND THE SPECIFIED MATERIALS ARE PROVEN THAT THE SPECIFIED MATERIAL IS NOT AVAILABLE. THE CONTRACTOR MUST PROVIDE NAME AND VARIETY OF SUBSTITUTION TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO TAGGING OR PLANTING. SUBSTITUTIONS MUST BE OF THE EQUIVALENT SIZE OF VARIETY OF PLANT HAVING SAME ESSENTIAL CHARACTERISTICS.
 5. ALL PLANT MATERIAL SHALL BE NURSERY GROWN, SOUND, HEALTHY, VIGOROUS, AND FREE FROM ALL DISEASE AND PESTS. THE MINIMUM AGE OF GROWTH THAT IS NORMAL FOR THE SPECIES. SIZES SHALL BE EQUAL TO OR EXCEEDING SIZES SPECIFIED ON THE PLANS. THE GROWTH SIZE AND QUALITY OF PLANT MATERIAL SHALL CONFORM TO THE ARIZONA STANDARD NURSERY STOCK (ANSI Z60.1, MOST RECENT EDITION).
 6. ALL DISTURBED AREAS WITHIN CONTRACT LIMITS, NOT COVERED BY PAVING, BUILDINGS, OR PLANTING BEDS ARE TO BE SEEDDED WITH TURFGRASS OR BARRIENEN SEED MIX.
 7. THE CONTRACTOR SHALL PROTECT SUBSURFACE SOIL OR DRAINAGE FROM EROSION TO THE LANDSCAPE ARCHITECT PRIOR TO PLANTING.
 8. REFER TO PLANTING DETAILS FOR PROPER METHODS OF INSTALLING PLANT MATERIALS.
 9. SEE SPECIFICATIONS FOR PLANT MAINTENANCE AND WARRANTY REQUIREMENTS.
 10. CONTRACTOR TO PROVIDE TEMPORARY WATERING SYSTEM OR WATER TRUCK DURING WARRANTY PERIOD TO DELIVER ADEQUATE MOISTURE TO PLANT MATERIALS TO ENSURE PROPER ROOT GROWTH.
 11. UTILIZE SODAS SPECIFICATIONS FOR LANDSCAPING.

OPEN SPACE AND LANDSCAPE REQUIREMENTS PER CITY
OF ANKENY CODE:

1. NOT LESS THAN 20% OF GROSS LAND AREA INCLUDED IN THE BUILDING LOT SHALL BE DEVOTED TO OPEN SPACE.

2. TREES AND SHRUBS SHALL BE PROVIDED AT A MINIMUM OF ONE LANDSCAPE UNIT PER 3,000 SQUARE FEET OF REQUIRED OPEN SPACE. ONE LANDSCAPE UNIT CONSISTS OF 2 TREES AND 6 SHRUBS, OR 3 TREES AND 3 SHRUBS.
3. GROSS LAND AREA = 72,309.6 SF
4. 20% OPEN SPACE REQUIREMENT = $72,309.6 \times 20\% = 14,461.9\text{ SF}$.
5. LANDSCAPE UNITS = $14,461.9 / 3,000 = 4.8$
6. REQUIRED TREES = $4.8 \times 2 = 9.6$, 10 TREES REQUIRED, 10 TREES PROVIDED.
7. REQUIRED SHRUBS = $4.8 \times 6 = 28.8$, 29 SHRUBS REQUIRED, 30 SHRUBS PROVIDED.

SHADING TREE CALCULATION:

1. GROSS PAVED AREA $\times 0.2$ = REQUIRED SHADING AREA.
2. REQUIRED SHADING AREA / 706 SF = SHADING TREES REQUIRED.
3. PAVED AREA = 20,753.4 SF
4. REQUIRED SHADING AREA = 20,753.4 $\times 0.2$ = 4,150.7
5. 4,150.7 SF / 706 SF = 5.9 TREES. 6 SHADE TREES REQUIRED, 6 SHADE TREES PROVIDED.



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

			PROJECT MANAGER	R. BAKER
			CIVIL	G. NORTON
			PROCESS	R. BAKER
			STRUCTURAL	D. WISEMAN
			ELECTRICAL	K. BOYD
4	03-10-2023	100% REVIEW SET		
3	02-08-2023	80% INTERNAL REVIEW SET		
2	12-21-2022	80% CLIENT REVIEW SET		
1	09-08-2022	50% REVIEW SET		
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	10345779

PRELIMINARY
NOT FOR
CONSTRUCTION

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

SITE LANDSCAPE PLAN



FILENAME	10L101.dwg
SCALE	1" = 20'

SHEET
10L101



10L501.dwg
7/12/2023 3:50 PM
KeyHill Plot



300 E LOCUST ST. SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-09-2023	90% INTERIM REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

LANDSCAPE DETAILS



FILENAME | 10L501.dwg
SCALE | NO SCALE

SHEET
10L501




300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINEDALE DRIVE
ELEVATED WATER
STORAGE TANK

**SITE PLANNING
SITE PIPING PLAN**



FILENAME | 10D101.dwg
SCALE | 1" = 20'

SHEET
10D101



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4840

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




**CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINEDALE DRIVE
ELEVATED WATER
STORAGE TANK**

**SITE PLANNING
SITE ELECTRICAL PLAN**

FILENAME 10E101.dwg
SCALE 1" = 20'

SHEET
10E101



20U101.dwg
3/12/2023 8:51 AM
Keyfile Plot



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER		R. BAKER
CIVIL	G. NORTON	
PROCESS	R. BAKER	
STRUCTURAL	D. WISEMAN	
ELECTRICAL	K. BOYD	
PROJECT NUMBER		10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

COMPOSITE ELEVATED STORAGE TANK
(BASE BID)
STRUCTURAL AND PROCESS PLANS

0 1" 2"
SCALE AS NOTED

FILENAME 20U101.dwg

SHEET
20U101



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	03-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	80% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

**COMPOSITE ELEVATED STORAGE TANK
(BASE BID)
STRUCTURAL AND PROCESS
SECTION AND ELEVATION**

FILENAME | 20U301.dwg
SCALE | AS NOTED

SHEET
20U301



20E101.dwg
2/16/2023 1:21 PM
Koyul Park



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	90% REVIEW SET

PROJECT MANAGER R. BAKER	
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER 10345779	

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023



CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

COMPOSITE ELEVATED STORAGE TANK
(BASE BID)
ELECTRICAL PLAN AND SECTION



FILENAME 20E101.dwg
SCALE AS NOTED

SHEET
20E101

300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-09-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANKCOMPOSITE ELEVATED STORAGE TANK
(BASE BID)
ONE LINE DIAGRAM AND SCHEDULEFILENAME | 20E601.dwg
SCALE | AS NOTEDSHEET
20E601

LIGHTING FIXTURE SCHEDULE


SYMBOL	DESCRIPTION	FIXTURE		MOUNTING	NOTES
		TYPE	WATTS		
	WET AREA FIXTURE INTERIOR LANDINGS / MANWAY HOUSING: CAST ALUMINUM GUARD, PLATINUM SILVER OPTICS: CLEAR GLASS PROTECTIVE GLOBE MFR: HUBBELL VAPORTITE VWG-150	LED	1500 MIN	TOWER INTERIOR, DIRECT TO CONDUIT FITTING/DEVICE BOX	INDUSTRIAL, LOW TEMP, LED BULB TO BE STANDARD SIZED WITH 100W INCANDESCENCE EQUIVALENCY, 1500 LUMEN MINIMUM, 4K TEMPERATURE TO MATCH OTHER FIXTURES OUTPUT COLOR
	ARCHITECTURAL TRAPEZOIDAL WALLPACK HOUSING: ALUMINUM, BLACK OPTICS: VISUAL COMFORT FORWARD THROW OPTIONS: INTEGRAL PHOTOCELL MFR: LITHONIA WST LED P1 40K VF 120 SF DBLXD	LED	1,639 12	SURFACE / WALL	OPTION LEGEND B1 = LIGHT ONLY B2 = LIGHT W/MOTION/AMBIENT SENSOR B3 = LIGHT W/ BATTERY B4 = LIGHT W/MOTION/SENSOR & BATTERY
	OUTDOOR POLE MOUNTED, 18" RD TAPERED ALUMINUM POLE HOUSING: ALUMINUM, BLACK OPTICS: TYPE III MEDIUM PICOPRISM OPTIONS: SINGLE FUSE, INTEGRAL MOTION/AMBIENT SENSOR MFR: HUBBELL 15A-ALT3-P35-120L-4K-120-BL-A30-SF-SCH-R	LED	15538 144	POLE / WALL	40K COLOR TEMPERATURE

KEYNOTES


- CONTRACTOR TO COORDINATE WITH JETCO AT (515-867-5874) TO FURNISH A SCADA RADIO/RTU (PLC-1) AT THE NEW WATER TOWER ELECTRICAL EQUIPMENT RACK. CONTRACTOR SHALL INSTALL THE ANTENNA AND PRESSURE TRANSDUCER WIRES AND CONDUITS REQUIRED TO TRANSMIT WATER LEVEL READING TO SCADA SYSTEM. JETCO WILL FURNISH SCADA RADIO/RTU PANEL, ANTENNA AND ANTENNA CABLE, AND PRESSURE TRANSDUCER TO CONTRACTOR FOR INSTALLATION. JETCO WILL ALSO PROVIDE PROGRAMMING FOR PLC AND CITY SCADA SYSTEM.

GENERAL NOTES

- CALL MIDAMERICAN ENERGY AT (MATT NOVY 515-882-8730) FOR COORDINATING ELECTRICAL SERVICE INSTALLATION. SERVICE FEES WILL BE PAID BY CITY OF ANKENY DIRECTLY.
- INSTALL ALL DEVICES, MATERIAL AND EQUIPMENT PER THE LATEST NEC REQUIREMENTS FOR A COMPLETE AND OPERATIONAL SYSTEM.
- INSTALL A COMPLETE GROUNDING SYSTEM PER THE LATEST NEC REQUIREMENTS, SEE SHEET 20E601.
- SEE PLAN (SHEET 20E101) FOR ELECTRICAL PANEL LOCATION, AND SHEET 10E101 FOR POWER POLE LOCATION.
- SEE ELECTRICAL ELEVATION DRAWING (SHEET 20E101) FOR LUMINAIRE LOCATIONS AND TANK GROUNDING DETAILS.



PANEL DESIGNATION: TANK LIGHTING PANEL "LP-1"				LOCATION: MCC			
VOLTAGE: 120/240V, 1PH,3W				MAIN: 100A MAIN CIRCUIT BREAKER			
AMPERES: 100				PANEL MOUNTING: SURFACE			
LOAD SERVED	CONNECTED LOAD (VA)		CIRCUIT BREAKER	CKT NO.	SEE MAIN	CIRCUIT BREAKER	LOAD SERVED
	L1	L2					
TVSS	-	-	30 2	1	-	2 1 20	RECEPTACLES
RTU	500	-	20 1 5	5	-	4 1 60	BULK WATER STATION
SPARE	-	-	20 2 7	7	-	6 1 20*	INTERIOR TANK LIGHTING
HEAT TRACE	1200	20**	1 11	11	-	8 1 20	OBSTRUCTION LIGHT
SPARE	-	-	20 1 13	13	-	10 1 20**	EXTERIOR AREA LIGHTS
SPARE	-	-	-	15	-	12 1 20	EXTERIOR TANK LIGHTING
SPARE	-	-	-	17	-	14 1 20	SPARE
SPARE	-	-	-	19	-	16 1 -	SPARE
SPARE	-	-	-	19	-	18 1 -	SPARE
SPARE	-	-	-	19	-	20 1 -	SPARE
SUB-TOTAL				500	1200	1537 3260	SUB-TOTAL
L1: 2037 KVA = 17.0 AMPS				TOTAL CONNECTED LOAD = 6.5 KVA:			
L2: 4460 KVA = 37.2 AMPS				NOTE:			
				NEUA 4 ENCLOSURE			
				BREAKERS DENOTED BY AN * SHALL BE GF TYPE			
				BREAKER DENOTED BY AN ** SHALL BE GFEP TYPE			



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-09-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED. THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

HYDROPIILLAR ELEVATED STORAGE TANK
(BID ALTERNATE NO. 1)
STRUCTURAL AND PROCESS PLANS



FILENAME | 21U101.dwg
SCALE | AS NOTED

SHEET
21U101



300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**

ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023





**CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK**

**HYDROPIILLAR ELEVATED STORAGE TANK
(BID ALTERNATE NO. 1)
STRUCTURAL AND PROCESS
SECTION AND ELEVATION**

FILENAME 21U301.dwg
SCALE AS NOTED

SHEET
21U301




GENERAL NOTES:

1. ALL ELECTRICAL CONSTRUCTION SHALL CONFORM WITH CURRENT NFPA 70 (NEC) STANDARDS.
2. PROVIDE RACEWAYS AND ELECTRICAL CONDUIT FOR LIGHTS AS DENOTED IN THE DRAWINGS AND SPECIFICATIONS. INSTALL ELECTRICAL EQUIPMENT RACK INSIDE TANK PEDESTAL.
3. RACEWAYS AND CONDUITS SHALL NOT BE ATTACHED TO THE LADDER.
4. SEE SHEET 20E01 FOR LIGHT FIXTURE SCHEDULE AND DIAGRAM.

KEYNOTES: (B)


1. MOUNT LIGHT FIXTURES AT ELEVATIONS SHOWN. 2' EITHER SIDE OF LADDER (TYPE B OVER DOORWAY). POWER FROM SWITCH LOCATED INSIDE DOORWAY.
2. HEAT TRACING AND PIPE INSULATION SHALL BE INSTALLED ON 3\"/>



300 E LOCUST ST. SUITE #210
DES MOINES, IA 50309
515-280-4940

PROJECT MANAGER R. BAKER		
CIVIL G. NORTON		
PROCESS R. BAKER		
STRUCTURAL D. WISEMAN		
ELECTRICAL K. BOYD		
PROJECT NUMBER 10345779		
ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

**PRELIMINARY
NOT FOR
CONSTRUCTION**
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT





CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK


HYDROPILLAR ELEVATED STORAGE TANK
(BID ALTERNATE NO. 1)
ELECTRICAL PLAN AND SECTION

FILENAME 21E101.dwg
SCALE AS NOTED

SHEET
21E101







- NOTES:**
1. ALL HOOKS SHALL BE STD 90 DEGREE HOOKS.
 2. SEE DRAWINGS FOR ADDITIONAL HORIZONTAL BARS. STAGGER BETWEEN TYPICAL REINF SPACING. EXTEND TO 1/5 OF DISTANCE TO NEAREST ADJACENT WALL IN EACH DIRECTION, UNCL.
 3. OPTIONAL LAP LOCATION, APPLIES TO BOTH DOUBLE AND SINGLE LAYER CONDITIONS TYP.



- GENERAL NOTES:**
1. COORDINATE FOUNDATION DIMENSIONS, PENETRATIONS, AND EMBEDMENTS WITH EQUIPMENT FURNISHED.
 2. ANCHOR BOLT DIA AND LOCATION BY EQUIPMENT MANUFACTURER.
 3. DESIGN PROPERTIES:
Fm=4,500 PSI (REINFORCED CAST-IN-PLACE)
Fy=60,000 PSI
 4. REQUIRED SOIL BEARING CAPACITY AT PERIMETER = 1,500 PSF
 5. CONCRETE COVER:
CONCRETE DEPOSITED AGAINST EARTH: 3"
ALL OTHER: 2"
 6. PROVIDE 3/4" CHAMFERS AT ALL EXPOSED EDGES.
 7. SEE SHEET 10C101 FOR FOUNDATION SITE LAYOUT AND COORDINATE INFORMATION.
 8. SEE SHEET 30U102 FOR PACKAGE BULK WATER STATION BUILDING INFORMATION.
 9. FINISH GRADE ABUTTING FOUNDATION SHALL BE MINIMUM 6" BELOW TOP OF FOUNDATION AND SLOPE AWAY FROM THE FOUNDATION WITHOUT CREATING WATER PONDING CONDITION.

- KEYNOTES:** (B)
1. PROVIDE 1 1/2" CONDUIT (MAIN POWER) AND 3 SPARE 1 1/2" CONDUITS THROUGH 8" x 14" BLOCKOUT IN CONCRETE FLOOR AND IN FOUNDATION 24" BELOW FINISH GRADE.
 2. BULK WATER STATION BUILDING SHALL BE 3' OFF ROAD PAVEMENT AND 6-8 INCHES ABOVE ROAD PAVEMENT.



- ANCHORAGE NOTES:**
1. ANCHORAGE INCLUDING CLIPS AND ANCHOR BOLT SIZE SHALL BE DESIGNED BY BUILDING MANUFACTURER
 2. ANCHOR CLIPS SHALL BE FURNISHED BY BUILDING MANUFACTURER.
 3. ANCHOR BOLTS AND NUTS SHALL BE FURNISHED AND INSTALLED BY CONTRACTOR.
 4. MINIMUM EDGE DISTANCE SHALL BE 10" AS REQUIRED BY BUILDING MANUFACTURER'S ANCHOR BOLT DESIGN EDGE DISTANCE.
 5. INSTALL SHIMS AT PERIMETER OF FRAME AS RECOMMENDED BY BUILDING MANUFACTURER AND AS REQUIRED TO LEVEL FRAME. TACK AND WELD ALL SHIMS AND FINISH PAINT.

TYPICAL ANCHOR DETAIL
NOT TO SCALE

30U101.dwg
7/12/2023 3:51 PM
Keyfill Plot




300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER	R. BAKER
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER	10345779

**PRELIMINARY
NOT FOR
CONSTRUCTION**
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023




CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

**BULK WATER SALES STATION
STRUCTURAL FOUNDATION PLAN
SECTIONS AND DETAILS**

FILENAME | 30U101.dwg
SCALE | AS INDICATED


SHEET
30U101

1 2 3 4 5 6 7 8




SECTION
1/2" = 1'-0"

- NOTE:
1. ALL EXTERIOR BURIED WATER PIPING SHALL BE RESTRAINED JOINT PIPE.



SECTION
1/2" = 1'-0"



PLAN VIEW
1/2" = 1'-0"

GENERAL NOTES:

1. COORDINATE BUILDING DIMENSIONS, PENETRATIONS, AND EMBEDMENTS WITH FOUNDATION PLAN.
2. SEE SHEET 10C101 FOR FOUNDATION SITE LAYOUT AND COORDINATE INFORMATION.
3. SEE SHEET 30U101 FOR PACKAGE BULK WATER PUMP STATION FOUNDATION INFORMATION.
4. ALL PIPING AND EQUIPMENT WILL BE ADEQUATELY SUPPORTED AND BRACED.
5. ALL BURIED WATER MAIN SHALL BE RESTRAINED.
6. EXCEPT FOR PIPE END SUPPORTS, WHICH ARE SHOWN, VERTICAL AND ANGLE PIPE BRACES ARE NOT SHOWN FOR CLARITY.

30U102.dwg
2/15/2023 3:53 AM
Koychik Pwt




300 E LOCUST ST, SUITE #210
DES MOINES, IA 50309
515-280-4940

ISSUE	DATE	DESCRIPTION
4	03-10-2023	100% REVIEW SET
3	02-08-2023	90% INTERNAL REVIEW SET
2	12-21-2022	90% CLIENT REVIEW SET
1	09-08-2022	50% REVIEW SET

PROJECT MANAGER R. BAKER	
CIVIL	G. NORTON
PROCESS	R. BAKER
STRUCTURAL	D. WISEMAN
ELECTRICAL	K. BOYD
PROJECT NUMBER 10345779	

PRELIMINARY
NOT FOR
CONSTRUCTION
ELECTRONIC SEAL & SIGNATURE HAVE BEEN
REMOVED, THIS SHOULD NOT BE CONSIDERED A
CERTIFIED DOCUMENT

03-2023



CITY OF ANKENY
POLK COUNTY, IOWA
NW IRVINGDALE DRIVE
ELEVATED WATER
STORAGE TANK

BULK WATER SALES STATION
PROCESS AND ELECTRICAL
PLANS AND SECTIONS

SCALE AS INDICATED

SHEET
30U102



**CITY OF ANKENY
ZONING BOARD OF ADJUSTMENT
COMMUNITY DEVELOPMENT DEPARTMENT STAFF REPORT**

To: Members of the Zoning Board of Adjustment
From: Bryan Morrissey, Associate Planner
Filing #: 23-11 EJC
Meeting Date: June 20, 2023
Address: 3755 NW Irvinedale Drive

APPELLANT REQUEST

A variance to Ankeny Municipal Code section 192.08(3)(G) that requires Maximum Height: 35 feet, allowing for the construction of a 180-foot-tall water tower at 3755 NW Irvinedale Drive.

STAFF POSITION

That the Zoning Board of Adjustment grant a variance to Ankeny Municipal Code Section 192.08(3)(G) to allow for the construction of a 180-foot-tall water tower at 3755 NW Irvinedale Drive.

Staff's position is based on a determination that the increased maximum height allowance from the resulting water tower would not impair adequate supply of air and light, would not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code.

PROJECT SUMMARY

The subject property is located at 3755 NW Irvinedale Drive, just north of the NW 36th Street and NW Irvinedale Drive intersection. The subject parcel is currently undeveloped and is zoned C-1, Neighborhood Retail Commercial District. The property is bordered by a gas station to the south and residential properties to the north and east. The parcel was acquired by the City of Ankeny in 2018 and has been the anticipated site for a future water tower for a number of years. Plans for the water tower are currently being reviewed and modified by both City Staff and an outside engineering firm. The City has decided that now is the appropriate time to request a variance to Ankeny Municipal Code Section 192.08(3)(G) to exceed the 35-foot maximum height allowance by 145 feet to construct an approximate 180-foot-tall water tower. Should the request for a variance be granted, the future final plat and site plan will need approval from the Plan & Zoning Commission and City Council prior to any construction on the site.

PROJECT REPORT

Criteria for Variance

197.01(4) Powers and Duties.

B. To grant a variation in the regulations when a property owner can show ...that by reason of exceptional narrowness, shallowness, or shape of a specific piece of property or by reason of exceptional topographical conditions or other extraordinary or exceptional situation, the strict application of the terms of this title actually prohibits the use of this property in the district; and that the board is satisfied under the evidence before it that a literal enforcement of the provisions of this title would result in unnecessary hardship; provided, however, that all variations granted under this clause shall be in harmony with the intended spirit and purpose of this title.

FINDINGS OF FACT

The subject property at 3755 NW Irvinedale Drive is generally located north of NW 36th Street and east of NW Irvinedale Drive, immediately north of the Casey's General Store in the area. The subject property is approximately 1.66 acres in size, is zoned C-1, Neighborhood Retail Commercial District, and is currently undeveloped. In addition to the gas station to the south, the subject property is bordered by residential properties to the north and east. The undeveloped parcel has been the presumed site for a future water tower for some time, as the City of Ankeny purchased the site back in 2018. With development in the northwestern quadrant of the City progressing over the years, the subject site is seen as an appropriate location to serve the future needs of Ankeny's residents. A future final plat and site plan are required before any construction on the project can begin; however, a variance to the C-1 Zoning District's height restriction of 35 feet is needed prior to any plans receiving approval.

As indicated on the applicant's submittal, the proposed water tower is expected to reach a maximum of 180 feet in height, which is similar in size to the existing water towers on SW Irvinedale Drive and NW Ash Drive. The proposed tower will be located near the eastern property line, away from NW Irvinedale Drive. Access drives off NW Irvinedale Drive will allow City employees to access the water tower facility for maintenance purposes. Additionally, landscaping and fencing is proposed near the north and east property lines, along with existing greenery that will provide a sense of separation between the future water tower and the neighboring residential properties.



Proposed Project Site at 3755 NW Irvinedale Drive

Staff does not have concerns with the water tower exceeding the maximum height allowance in the C-1 Zoning District, as this is something that has not only been permitted previously, but is considered a necessity when considering Ankeny's anticipated growth. The building of similar towers has been permitted in the past with the construction of the water towers on SW Irvinedale Drive and NW Ash Drive. Staff considers the construction of this water tower to be essential when considering the growth Ankeny has experienced since the last tower was completed in 2008, particularly on the City's northwest side. As mentioned previously, a water tower on the subject parcel has been planned for some time, with signage being present on the site notifying residents of the future water tower project for multiple years.



Existing Water Tower at 1841 SW Irvinedale Drive

Furthermore, similar variance requests have been approved by the Zoning Board of Adjustment in the past. The most recent being in 2008 which allowed the City to surpass a 45-foot height limitation to construct a 173-foot-tall water tower at 1841 SW Irvinedale Drive. As is standard procedure for these kinds of requests, property owners within 250' of the subject property were notified of the proposed variance by mail, and to date, staff has not received any correspondence either for or against the variance.

The staff position is to grant a variance to Ankeny Municipal Code Section 192.08(3)(G) to allow for the construction of a 180-foot tall water tower at 3755 NW Irvinedale Drive. Staff's position is based on a determination that the increased maximum height allowance from the resulting water tower would not impair adequate supply of air and light, would not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code.



ZONING BOARD OF ADJUSTMENT

June 20, 2023

5 : 00 PM

 [Print](#)

ORIGINATING DEPARTMENT:

Planning and Building

COUNCIL GOAL:

Ensure Economic Vitality

ACTION REQUESTED:

Public Hearing

LEGAL:

SUBJECT:

#23-12

Bryon and Larissa Weyer

for property located at

2506 NE 17th Street

Lot 21, Deer Creek Estates Plat 13

RE: Variance - Rear Yard Setback

EXECUTIVE SUMMARY:

FISCAL IMPACT: **No**

STAFF RECOMMENDATIONS:

PREVIOUS COUNCIL/COMMISSION/BOARD ACTION(S):


PUBLIC OUTREACH EFFORTS:

ACTION REQUESTED:

ADDITIONAL INFORMATION:

ATTACHMENTS:

Click to download
 #23-12 Applicant Submittal
 #23-12 Staff Report



#23-12

APPLICATION FOR APPEAL ZONING BOARD OF ADJUSTMENT

Applicant is: ☒ Property Owner ☐ Tenant ☐ Other _____

Applicant Bryon and Larissa Weyer

Address / Phone # 2506 NE 17th Street, Ankeny, IA 50021 /

E-mail bryonweyer27@gmail.com

Property Owner Bryon and Larissa Weyer

Address / Phone # 2506 NE 17th Street, Ankeny, IA 50021 /

E-mail bryonweyer27@gmail.com

(Owner must sign the application or submit a letter of authorization)

To the Members of the Board of Adjustment:

I hereby appeal from the decision of the Zoning Administrator rendered on 31 day of May, 2023

Location (address) of the proposed variance 2506 NE 17th St, Ankeny IA 50021

Legal description (Plat & Lot #) LOT 21 DEER CREEK ESTATES PLAT 13

Zoning R2 Principal Use of property Residence

I request a variation from the current zoning requirement for:

☐ Front Yard ☐ Side Yard ☒ Rear Yard ☐ Fence ☐ Sign ☐ Parking ☐ Height
☐ Other _____

Ankeny Zoning code Section # _____ which state(s) 35ft set back from rear property line

I would propose the following in lieu of that required: Covered patio 29ft from rear property line

Attached hereto and made a part of this appeal, I submit the following:

- a) A statement indicating the reasons for my appeal.
- b) A drawing showing proposed variance requested.
- c) A letter of authorization from the owner or lessee, if applicable.

Complete submittals are required for review.

AFFIDAVIT

State of Iowa)ss
County of Polk)

I hereby deposit and say that all of the above statements and the statements contained in the papers submitted herewith are true.

Larissa Weyer
(Signature of Applicant)



Signed and sworn to before me, this
31st day of May, 2023.
Brenda Fuglsang
(Notary Public)

RECEIVED		Office Use Only	
Date received _____	Paid ☐ Cash ☒ Check # <u>cc \$120.00</u>		
Filing # <u>23-12</u> MAY 31 2023	Scheduled Meeting Date <u>6-20-2023</u>		

CITY OF ANKENY

Brenda Fuglsang

#23-12

From: Bryon Weyer <bryonweyer27@gmail.com>
Sent: Wednesday, May 31, 2023 8:14 PM
To: Brenda Fuglsang
Subject: [External] Weyer Variance Description
Attachments: Variance Description.docx

CAUTION: This email originated from outside of the organization. Do not click links or open attachments unless you recognize the sender and know the content is safe.


Hi Brenda - please find the variance description attached to go with our application that was submitted today.

Thanks for your help!
Larissa & Bryon Weyer


Bryon and Larissa Weyer
2506 NE 17th Street
Ankeny, IA 50021


We are requesting a variance to the 35-foot set back from rear property line code. We would like to add a covered patio to the back of our house. The structure would be 14 feet deep which be 29 feet from our back property line.

#23-12



#23-12





N



1 inch = 152 feet

Date: 6/7/2023

**2506 NE 17th Street
Rear-Yard Setback Variance
Aerial Map**

**CITY OF ANKENY
ZONING BOARD OF ADJUSTMENT
COMMUNITY DEVELOPMENT DEPARTMENT STAFF REPORT**

To: Members of the Zoning Board of Adjustment
From: Ryan Kirschman, Planner
Filing #: 23-12 EJC
Meeting Date: June 20, 2023
Address: 2506 NE 17th Street

APPELLANT REQUEST

A variance to Ankeny Municipal Code Section 192.04(3)(E) that requires Rear Yard: 35-feet, allowing a 29-foot rear yard setback for a covered patio at 2506 NE 17th Street.

STAFF POSITION

Staff recommends the Zoning Board of Adjustment grant a variance to Ankeny Municipal Code Section 192.04(3)(E) to allow a 29-foot rear yard setback for the construction of a covered patio at 2506 NE 17th Street.

Staff's position is based on a determination that the decreased rear yard setback from the resulting covered patio would not impair adequate supply of air and light, would not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code.

PROJECT SUMMARY

The subject property is located at 2506 NE 17th Street, south of NE 18th Street and west of NE Four Mile Drive within the northeastern quadrant of Ankeny. The subject property is zoned R-2 with restrictions, One and Two-Family Residence District restricted to single family homes and is situated on Lot 21 Deer Creek Estates Plat 13.

The applicant is requesting a variance to encroach approximately 6-feet into the 35-foot rear yard setback that will allow the owners to convert their proposed patio into a covered patio. The patio is already constructed. Should the variance for the covered patio be approved, a 29-foot rear yard setback will be the resulting setback on the west side of the property.

PROJECT REPORT

Criteria for Variance

197.01(4) Powers and Duties.

B. To grant a variation in the regulations when a property owner can show ...that by reason of exceptional narrowness, shallowness, or shape of a specific piece of property or by reason of exceptional topographical conditions or other extraordinary or exceptional situation, the strict application of the terms of this title actually prohibits the use of this property in the district; and that the board is satisfied under the evidence before it that a literal enforcement of the provisions of this title would result in unnecessary hardship; provided, however, that all variations granted under this clause shall be in harmony with the intended spirit and purpose of this title.

FINDINGS OF FACT

The subject property is located at 2506 NE 17th Street, south of NE 18th Street and west of NE Four Mile Drive within the northeastern quadrant of Ankeny. The subject property is zoned R-2 with restrictions, One and Two-Family Residence District restricted to single family homes and contains a single-family home with an attached patio on the north side of the .289-acre lot. Neighboring properties to the north are zoned R-1, Single-Family Residence District, Properties to the east, south, and west are also zoned R-2 with restrictions and contain single family homes on similarly sized lots. Permit records show the house started construction in 2015 and was completed in 2016. Per Ankeny Municipal Code Section 196.03(2)(B) unenclosed patios are allowed to extend up to twelve feet into the rear yard setbacks, while covered patios are not permitted in rear yard setbacks.

As indicated by the applicant on their submitted site plan, at its furthest point the proposed covered patio extends approximately 6' into the rear yard setback leaving approximately 29' between the patio and the rear property line. Staff is not concerned with the covered patio extending into the rear-yard setback as the property backs to a 30' wide buffer of open space owned by the homeowners association and then NE 18th Street. Additionally, the covered patio should not have any measurable impact on surrounding residences.

Furthermore, similar variance requests have been approved by the Zoning Board of Adjustment in the past. The most recent being in May of 2023, which allowed a covered deck to extend 10-feet into the rear yard setback. As is standard procedure for these kinds of requests, all property owners within 250' of the subject property were notified of the proposed variance by mail, and to date, staff has not received any correspondence either for or against the variance.

The staff position is to grant a variance to Ankeny Municipal Code Section 192.04(3)(E) to allow a 29-foot rear yard setback for the construction of a covered patio at 2506 NE 17th Street. Staff's position is based on a determination that the decreased rear yard setback from the resulting covered patio would not impair adequate supply of air and light, would not increase public danger of fire, or diminish property values; and that this request is in harmony with the intended spirit and purpose of the Ankeny Municipal Code.

192.04(3)(E) Size and Area Regulations.

C. Rear Yard: 35 feet

196.03(2)(B) Yard Setback Exceptions

(2) Rear Yard. Unenclosed, above and below, decks which project not more than 12-feet into the required rear yard.



ZONING BOARD OF ADJUSTMENT

June 20, 2023

5 : 00 PM



ORIGINATING DEPARTMENT:

Planning and Building

COUNCIL GOAL:

ACTION REQUESTED:

LEGAL:

SUBJECT:

Renewed Special Use Permits

#10-06 Lindo Jalisco Mexican, 1810 SW White Birch Circle, Ste. 118

#21-06 El Molcajete, 301 E 1st Street

#16-16 Guadalajara Mexican Restaurant, 202 SE Delaware Avenue

#18-04(2019) Who's on First, 810 E 1st Street

EXECUTIVE SUMMARY:

FISCAL IMPACT: **No**

STAFF RECOMMENDATIONS:

PREVIOUS COUNCIL/COMMISSION/BOARD ACTION(S):


PUBLIC OUTREACH EFFORTS:

ACTION REQUESTED:

ADDITIONAL INFORMATION:

ATTACHMENTS:

Click to download
 Special Use Permit Renewals



City of Ankeny

Outdoor Service Area Renewal Application

***Original Special Permit Resolution # 10-06**

If the conditions of your approved Special Use Permit do not allow for administrative approval of the Outdoor Service Area, or if you plan to make any changes or would like to alter the conditions of your Outdoor Service Area, please contact the Planning & Building Department (963-3550) regarding the required Board of Adjustment approval.

Name of Applicant: Primos Iowa, LLC
(Sole Proprietorship, Partnership, Corporation)

Name of Business (d/b/a): Lindo Jalisco Mexican

Address of Premise: 1810 SW White Birch Cir., Ste. 118

- Have there been any changes made to the Outdoor Service Area since last year in location, size, or type of fencing?

☐ Yes ☒ No

If yes, what changes have been made. (Please include a sketch)


- Has any use of sound been added since last year or changed from what was approved by the Zoning Board of Adjustment?

☐ Yes ☒ No

Examples of sound uses requiring a special use permit shall include but not be limited to use of speakers to page patrons, use of a sound system to play music and the playing of live music. (Ord. 1426 Sec 1 Sub-section 5.08.100 G paragraph 5)

I hereby swear and affirm that I have complied and will continue to comply with all the requirements and attached conditions issued for the above identified property and with any subsequent modifications required by the Board of Adjustment.

The applicant hereby swears or affirms that all statements set forth herein are true and correct.


Signature
Abraham Murguia F
Name of Applicant (printed)

*(Copy of Original Resolution attached)

5/10/23
Date

ADMINISTRATIVELY
☒ **APPROVED**
5/15/23 EJC



City of Ankeny

Outdoor Service Area Renewal Application

***Special Permit Resolution # 21-06**

If the conditions of your approved Special Use Permit do not allow for administrative approval of the Outdoor Service Area, or if you plan to make any changes or would like to alter the conditions of your Outdoor Service Area, please contact the Planning & Building Department (963-3550) regarding the required Board of Adjustment approval.

Name of Applicant: Mi Pueblo 15 LLC
(Sole Proprietorship, Partnership, Corporation)

Name of Business (d/b/a): El Molcajete

Address of Premise: 301 E. 1st St.

- Have there been any changes made to the Outdoor Service Area since last year in location, size, or type of fencing?

☐ Yes ☒ No

If yes, what changes have been made. (Please include a sketch)

- Has any use of sound been added since last year or changed from what was approved by the Zoning Board of Adjustment?

☐ Yes ☒ No

Examples of sound uses requiring a special use permit shall include but not be limited to use of speakers to page patrons, use of a sound system to play music and the playing of live music. (Ord. 1426 Sec 1 Sub-section 5.08.100 G paragraph 5)

I hereby swear and affirm that I have complied and will continue to comply with all the requirements and attached conditions issued for the above identified property and with any subsequent modifications required by the Board of Adjustment.

The applicant hereby swears or affirms that all statements set forth herein are true and correct.

Abraham Murguía F
Signature

Abraham Murguía F
Name of Applicant (printed)

5/8/23
Date

ADMINISTRATIVELY



5/12/23 EJC



City of Ankeny

Outdoor Service Area Renewal Application

***Special Permit Resolution # 16-16**

Originally issued August 16, 2016

If the conditions of your approved Special Use Permit do not allow for administrative approval of the Outdoor Service Area, or if you plan to make any changes or would like to alter the conditions of your Outdoor Service Area, please contact the Planning & Building Department (963-3550) regarding the required Board of Adjustment approval.

Name of Applicant: Guadalajara, LLC
(Sole Proprietorship, Partnership, Corporation)

Name of Business (d/b/a): Guadalajara Mexican Restaurant

Address of Premise: 202 S. E. Delaware Ave.

- Have there been any changes made to the Outdoor Service Area since last year in location, size, or type of fencing?

☐ Yes ☒ No

If yes, what changes have been made. (Please include a sketch)


- Has any use of sound been added since last year or changed from what was approved by the Zoning Board of Adjustment?

☐ Yes ☒ No

Examples of sound uses requiring a special use permit shall include but not be limited to use of speakers to page patrons, use of a sound system to play music and the playing of live music. (Ord. 1426 Sec 1 Sub-section 5.08.100 G paragraph 5)

I hereby swear and affirm that I have complied and will continue to comply with all the requirements and attached conditions issued for the above identified property and with any subsequent modifications required by the Board of Adjustment.

The applicant hereby swears or affirms that all statements set forth herein are true and correct.



Signature


Jose Lopez

Name of Applicant (printed)

May 18, 2023

Date

ADMINISTRATIVELY
 **APPROVED**
5/25/23 ESC



City of Ankeny

Outdoor Service Area Renewal Application

***Special Permit Resolution # 18-04 (2019)**

If the conditions of your approved Special Use Permit do not allow for administrative approval of the Outdoor Service Area, or if you plan to make any changes or would like to alter the conditions of your Outdoor Service Area, please contact the Planning & Building Department (963-3550) regarding the required Board of Adjustment approval.

Name of Applicant: What's on Second
(Sole Proprietorship, Partnership, Corporation)

Name of Business (d/b/a): Who's on First

Address of Premise: 810 E 1st St.

- Have there been any changes made to the Outdoor Service Area since last year in location, size, or type of fencing?

☐ Yes ☒ No

If yes, what changes have been made. (Please include a sketch)


- Has any use of sound been added since last year or changed from what was approved by the Zoning Board of Adjustment?

☐ Yes ☒ No

Examples of sound uses requiring a special use permit shall include but not be limited to use of speakers to page patrons, use of a sound system to play music and the playing of live music. (Ord. 1426 Sec 1 Sub-section 5.08.100 G paragraph 5)

I hereby swear and affirm that I have complied and will continue to comply with all the requirements and attached conditions issued for the above identified property and with any subsequent modifications required by the Board of Adjustment.

The applicant hereby swears or affirms that all statements set forth herein are true and correct.


Signature
Aaron McCombs (Whos on first)
Name of Applicant (printed)

5/25/23
Date

ADMINISTRATIVELY
☒ **APPROVED**

6/8/23 ESC